

RFI Questions and Answers -

Bidders:

Please see the following bid questions and answers:

1. Have all permits been issued, including the items listed on Sheet T-1.2 which are the M., E., P., Vault, Retaining Wall and Block Wall. If not, are they actually all required? *Answer - Permits have been attained by the design team for all disciplines noted with the exception of the electrical permit which is still in progress. Approvals noted as Deferred Submittals are the responsibility of the Contractor.*
2. General Note # 14 on Sheet T-1.1 requires certification of key or bottom. Has this been done accordingly? Do we have to be concerned with pad or any grading certification? *Answer - Pad bottoms have been inspected by the listed engineer. Final grading has not been completed. Once completed by the contractor pad certification will be completed by City hired geotechnical engineer.*
3. The plans require perimeter over excavation and re-compaction, has this been completed? *Answer - Building pad over excavation and compaction has been completed and reviewed by the geotechnical engineer.*
4. In general are the grading, underground work and the existing completed work accepted by the City? *Answer - In general, grading, underground and work completed has been accepted by the City.*
5. Please verify if the 6' x 16' precast vault has been installed. *Answer - 6'x16' precast vault box only has been installed.*
6. Who will provide the future compressor (C-3) and Pump Station control panel (C-1)? *Answer - Compressor and control panel to be installed at a later date by the City and are not part of this contract.*
7. Can you provide the name for the Structural Steel supplier? *Answer - B.F. Steel, Inc. (1037 W. 251st Street, Harbor City, CA 90710), Phone : 310.539.3323.*