

TABLE OF CONTENTS

<u>Section I</u>	<u>General</u>
A.	Purpose
B.	Project Background
C.	Objectives
<u>Section II</u>	<u>Scope of Services</u>
<u>Section III</u>	<u>Bid Requirements</u>
<u>Section IV</u>	<u>Contractor Selection Guidelines</u>
<u>Section V</u>	<u>Sole Authority</u>
<u>Section VI</u>	<u>Deadline, Questions and Optional Site Tour</u>
<u>Section VII</u>	<u>Exhibits</u>

EXHIBIT A - Report of Percolation Testing prepared by GeoDesign, Inc. (07/13/09)

EXHIBIT B - As-Built for 1654-19th Street, Santa Monica California:

- 1) **Sheet 1, Floor Plan, Exterior Elevations & Building Section prepared by Birba Group (11/15/90)**
- 2) **Sheet 2, Roof Plan, Toilets and Details prepared by Birba Group**
- 3) **Sheet 3, Details prepared by Birba Group**
- 4) **Sheet 4, Details prepared by Birba Group**
- 5) **Sheet S-1, Structural Notes & Details prepared by er.Varas & Assoc. (04/26/091)**
- 6) **Sheet S-2, Structural Sections prepared by er.Varas & Assoc. (04/26/91)**
- 7) **Sheet S-3, Structural Details prepared by er.Varas & Associates (04/26/09)**
- 8) **Sheet S-4, Structural Plans prepared by er.Varas & Associates (04/26/09)**
- 9) **Sheet S-5, Roof Framing Plan prepared by er.Varas & Associates (04/26/91)**
- 10) **Sheet L-1, Irrigation and Planting Plan prepared by Lynn Capouya**
- 11) **Sheet L-2, Irrigation and Planting Plan prepared by Lynn Capouya**

EXHIBIT C - Southern California Edison drawings for 1654-19th Street in Santa Monica (08/07/09)

EXHIBIT D - Fire Hydrant Flow Tests Performed near 1654-19th Street on 09/01/09

EXHIBIT E - Bulk Asbestos and Lead Sampling Report prepared by SCA Environmental, Inc. (08/26/10)

EXHIBIT F - State of Arizona Disclosure Form

EXHIBIT G - Project Drawings Prepared by nonzero/architecture, Gordon Polon, ARC Engineering, Acentech, and TV Magic.

EXHIBIT H - Project Specifications Prepared by nonzero/architecture, Gordon Polon, ARC Engineering, Acentech, and TV Magic.

SECTION I. GENERAL

A. Purpose

The City of Santa Monica is soliciting bids from qualified contractors for construction services for the CityTV Tenant Improvement Project. This project is located at 1654-19th Street in Santa Monica.

B. Project Background

The existing building located at 1654-19th Street in Santa Monica is a CMU block building that was used as an auto repair shop. The building is approximately 4,700 square feet and contains vehicle bays, an office space, an auto parts storage area, a men's and women's restroom, and an attic space for storage. After the tenant improvements have been completed, the City of Santa Monica's government community cable channel, CityTV, will be moving into the building and using it as offices and a television studio.

C. Objectives

The City is seeking bids from contractors to provide construction services for tenant improvements at 1654-19th Street in Santa Monica. The contractor is responsible for the project meeting all federal, state and local agency regulations.

The construction contract duration is two hundred ten (210) calendar days, and the anticipated Notice to Proceed date is January 2011.

Note that this project is subject to prevailing wage rates, and the contractor is required to have **a Class A (General Engineering Contractor) or Class B (General Building Contractor) license** at the time of bid submission. This project may also be subject to the City of Santa Monica's Living Wage Ordinance and this form must be signed and submitted with the bid. The Oaks Initiative Disclosure Form and the State of Arizona Disclosure Form (Exhibit "F") must also be signed and submitted with the bid.

The contractor will be required to implement construction techniques for the project which increase life-cycle economic return, increase durability and longevity of building materials and systems, maximize construction worker and patron health and productivity, minimize resource use (including energy, water and materials), minimize waste, minimize site and neighborhood disruption, minimize pollution, and model the applicability of sustainable design and construction techniques. For further information on the City of Santa Monica's guidelines on sustainability, please visit the City's Internet site established at <http://greenbuildings.santa-monica.org>.

SECTION II. SCOPE OF SERVICES

For the scope of work, refer to the attached General Requirements and Exhibits "G" and "H" for the project drawings and specifications. The Work includes the construction of offices, an attic space and a television studio space. The scope of work includes, but is not limited to, demolition, structural upgrades to the building, new restrooms and a kitchen, a new mezzanine, a new building HVAC system, new fire sprinklers, phone and data network, cable television, audio visual system, electrical upgrades and installation of a storm drain system.

The contractor will be responsible for coordinating work with the utility companies for the new utility connections to the building.

All demolished material shall be removed and disposed by the contractor. The contractor must also submit a Construction Waste Management Plan and pay a performance security deposit (3% of the project valuation to a maximum deposit amount of \$30,000) as required per the City of Santa Monica's Construction and Demolition Ordinance (Ordinance 895 CCS), refer to the attached General Requirements specification section 01560.

Hours of construction are to be Monday thru Friday 7:00 am to 6:00 pm, Saturday 9:00 am to 5:00 pm.

There is limited street parking and parking on site at 1654-19th Street. If the contractor needs parking permits, the contractor is responsible for coordinating with the City's Transportation Management and Parking Office to obtain street parking permits. The contractor is responsible for any fees associated with parking vehicles and other construction equipment on the street.

SECTION III. BID REQUIREMENTS

The City has established requirements for bids in compliance with the Sustainable City Program to promote waste reduction and resource conservation. Submittals should not contain plastic bindings, plastic pages, or laminated pages. Double-sided bids are preferred. Copies should be printed on recycled and/or tree-free paper. Please avoid superfluous use of paper (such as separate title sheets or chapter dividers and unnecessary attachments or documents not specifically requested).

For consideration, please submit three (3) copies of the bid containing the following elements:

- A. Client reference list which indicates clients on projects similar to this project. Provide name of project, construction dates, name of client contact, position and contact number.
- B. A list of subcontractors, if any, proposed to assist the general contractor. This list shall also include the subcontractors' qualifications pertinent to this project.
- C. Submit the Bid Breakdown Form included in this RFB. Reimbursable expenses must be included. No additional fees will be considered for reimbursable expenses.
- D. A chart scheduling activities and proposed timetable for the activities including completion dates. The chart should be outlined by number of days to complete each task.

The selected contractor will be required to submit Proof of Insurance per the City's requirements contained in the Agreement, and a statement of liability for the accuracy, validity and reliability of services, including insurance coverage.

SECTION IV. CONTRACTOR SELECTION GUIDELINES

The review committee may include staff from CityTV, the Public Works Department and other City departments. Factors to be considered in reviewing bids may include but are not limited to:

1. General accomplishments and quality of work previously performed.
2. Previous history of work with similar projects.
3. Record of the contractor in accomplishing work within required time and budget constraints.
4. Understanding of the approach, tasks, and methodology necessary to complete the required services.
5. Geographical location of the project team.
6. References.
7. Costs included on the Bid Breakdown Form.
8. Costs/deductions included on the Add Alternate Form.

SECTION V. SOLE AUTHORITY

The City of Santa Monica has the sole authority to select the contractor, and reserves the right to reject any and all bids. By submitting a response to this RFB, prospective contractors waive the right to protest or seek legal remedies whatsoever regarding any aspect of this RFP. In addition, the City reserves the right to issue written notice to all participants of any changes in the bid submission schedule or submission requirements, should the City determine in sole and absolute discretion that such changes are necessary. The City also reserves the right to approve all individuals and firms, if any, to be retained by the prime contractor. The City's policy is to screen contractors based upon their bid and project reference checks.

SECTION VI. DEADLINE, QUESTIONS, AND OPTIONAL SITE TOUR

A. Deadline

In order to be considered, three (3) hard copies of the bid must be submitted **by 3:00 pm PST, Thursday, October 14, 2010 to:**

Office of the City Clerk
City Hall
1685 Main Street, Room 102
Santa Monica, CA 90401

Electronic copies of the bid will not be accepted.

B. Questions

Questions must be in writing and should be emailed to Karen Domerchie-Levine at karen.domerchie@smsgov.net. The last day to submit questions is by **5:00 pm on Friday, October 1, 2010.**

C. Site Tour

A site walk will be conducted on **Wednesday, September 29, 2010 at 10:00 AM.** Participation in this tour is not required, but is highly recommended, and is only to inform those bidders who wish to view the building so as to aid them in preparing an accurate cost bid. Interested parties should meet at 10:00am at 1654-19th Street in Santa Monica. Limited street parking is available on 19th Street, and metered street parking is available on Olympic Boulevard.

SECTION VII. EXHIBITS

Refer to following pages for exhibits.

EXHIBIT A - Report of Percolation Testing prepared by GeoDesign, Inc. (07/13/09)

EXHIBIT B - As-Built for 1654-19th Street, Santa Monica California:

- 1) **Sheet 1, Floor Plan, Exterior Elevations & Building Section prepared by Birba Group (11/15/90)**
- 2) **Sheet 2, Roof Plan, Toilets and Details prepared by Birba Group**
- 3) **Sheet 3, Details prepared by Birba Group**
- 4) **Sheet 4, Details prepared by Birba Group**
- 5) **Sheet S-1, Structural Notes & Details prepared by er.Varas & Assoc. (04/26/091)**
- 6) **Sheet S-2, Structural Sections prepared by er.Varas & Assoc. (04/26/91)**
- 7) **Sheet S-3, Structural Details prepared by er.Varas & Associates (04/26/09)**
- 8) **Sheet S-4, Structural Plans prepared by er.Varas & Associates (04/26/09)**
- 9) **Sheet S-5, Roof Framing Plan prepared by er.Varas & Associates (04/26/91)**
- 10) **Sheet L-1, Irrigation and Planting Plan prepared by Lynn Capouya**
- 11) **Sheet L-2, Irrigation and Planting Plan prepared by Lynn Capouya**

EXHIBIT C - Southern California Edison drawings for 1654-19th Street (08/07/09)

EXHIBIT D - Fire Hydrant Flow Tests Performed near 1654-19th Street on 09/01/09

EXHIBIT E - Bulk Asbestos/Lead Sampling Report prepared by SCA Environmental (08/26/10)

EXHIBIT F - State of Arizona Disclosure Form

EXHIBIT G - Project Drawings Prepared by nonzero/architecture, Gordon Polon, ARC Engineering, Acentech, and TV Magic.

EXHIBIT H - Project Specifications Prepared by nonzero/architecture, Gordon Polon, ARC Engineering, Acentech, and TV Magic.

July 13, 2009

City of Santa Monica
Architectural Services
1437 4th Street, Suite 300
Santa Monica, CA 90401

Attention: Ms. Karen Domerchie

Report of Percolation Testing
Proposed City TV Tenant Improvement Project
1654 19th Street
Santa Monica, California
GeoDesign Project: SMonica-6-01

INTRODUCTION

GeoDesign, Inc. is pleased to submit this report presenting the results of percolation testing for the proposed City TV Tenant Improvement Project located at 1654 19th Street in Santa Monica, California. The proposed project will consist of the conversion of the existing building located at 1654 19th Street in Santa Monica, California, for use as a television station and studio.

As part of the proposed renovation, a dry well system is planned at the east side (front) of the site, within the existing planter area, and a shallow trench infiltration system is planned at the west side (back) of the site.

The percolation testing was performed to provide design data for the proposed dry well and trench infiltration systems.

The location of the site relative to surrounding features is shown on Figure 1.

SCOPE OF SERVICES

Our completed scope of services is summarized as follows:

- Coordinated and managed the field investigation, including site access authorization and scheduling of drilling subcontractor and GeoDesign field staff.
- Drilled two borings to depths of approximately 40 and 50 feet below ground surface (BGS) using hollow-stem auger drilling equipment.
- Performed standard penetration tests in the borings at approximately 5-foot intervals.
- Obtained bulk samples from the borings, and maintained a log of the soil conditions encountered in each boring.
- Performed percolation testing in the borings at depths of approximately 20 and 35 feet BGS.
- Performed analysis of percolation test results.
- Prepared this report summarizing the results of our percolation testing.

SITE CONDITIONS

The site is bound on the east by 19th Street, on the west by an alley, and on the north and south by private property. The property to the north is occupied by a one-story, high-bay, brick building. The property to the south is occupied by one-story, single-family residence. The majority of this residential lot, immediately adjacent to the site, is vacant with no existing improvements.

On-site parking is on the front (east) side of the building and is accessed from 19th Street. The parking area is paved with concrete and is approximately 44 feet long by 50 feet wide. At-grade planters are located at the northeast and southeast corners of the entranceway, adjacent to the property boundary. Access to the rear (west) side of the existing building is from an alley (18th Court). There is one parking bay at the northwest corner of the building accessed from 18th Court.

The existing site conditions, including the limits of the existing building, planter areas, and adjacent streets, are shown on Figure 2.

GEOLOGIC CONDITONS

GENERAL

The site is located on the Sawtelle Plain, a younger Holocene-age alluvial apron originating from the Santa Monica Mountains to the north (California Division of Mines and Geology [CDMG], 1998 and California Department of Water Resources, 1961). In the area, the young sediments consist of predominantly fine-grained materials such as clay, silt, and fine sand and are generally less than 25 feet thick. These younger materials are underlain by older Pleistocene sediments that generally consist of alternating beds of dense to very dense sand and stiff silt and clay with abundant gravel present in most layers.

GROUNDWATER

Based on maps published by the California Geological Survey (formerly known as CDMG, 1998), the historic high groundwater level in the site vicinity is greater than 40 feet BGS.

Based on available water level information from Los Angeles County Department of Public Works, the nearest groundwater monitoring well is Well No. 2357, located approximately 3,000 feet east of the site. The available data for this well indicate that the depth to groundwater has fluctuated between 116 and 157 feet BGS during the 1971 to 1996 monitoring period. More recent data was not available.

FAULTS

The closest active fault to the site is the Santa Monica Fault, located approximately 1,600 feet north of the site (City of Santa Monica, 2001). The fault is known to act as a groundwater barrier in the area. Groundwater levels are generally higher on the north side of the fault relative to the south side. The site is located on the south side of the Santa Monica Fault.

FIELD INVESTIGATION

We drilled two borings using 8-inch, hollow-stem auger drilling equipment to depths of approximately 40 to 49.3 feet BGS at the site. Boring B-1 was drilled in the front (east side) of the existing building, within the existing planter, to a depth of 49.3 feet BGS. Boring B-2 was drilled at the rear of the building, within the parking stall at the northwest corner of the existing building, to a depth of 40 feet BGS. Upon completion of each boring, the holes were backfilled to the desired depth of the percolation test. The boring locations are shown on Figure 2.

SUBSURFACE CONDITIONS

The geologic materials encountered in our borings consist of alternating layers of relatively impermeable clay and silt and relatively high permeability, gravelly, silt and sand.

The upper 12 to 12.5 feet of materials consist of low permeability, medium stiff to very stiff clay and silt. Below the clay and silt, a layer of gravelly silt and sand with gravel was encountered to depths of approximately 19 to 20.5 feet BGS. The sand and gravelly silt is in turn underlain by alternating layers of less permeable silt and clay.

At a depth of 25.0 feet BGS in boring B-1 and 26.0 feet in boring B-2, the materials encountered consist of highly permeable, dense, fine sand to the maximum depth explored.

The following table provides a summary of the geologic materials at the site.

Table 1. Summary of Geologic Materials

Geologic Material	Boring (depth encountered, feet BGS)	
	B-1	B-2
Silt and Clay	0 - 12	0 - 12.5
Gravelly Silt/Sand with Gravel	12 - 19	12.5 - 20.5
Silt and Clay	19 - 25	20.5 - 26
Fine Sand	25 - 49.3	26 - 40

Groundwater was not encountered in our borings drilled to a maximum depth of 49.3 feet BGS.

After completion of drilling, the borings were backfilled with soil cuttings through the augers to prevent caving to a depth of 36.0 feet BGS in boring B-1 and 21.0 feet BGS in boring B-2. Twelve inches of bentonite chips were placed over the soil backfill and a 2-inch-diameter, screened pipe was set in each hole. The upper 10 feet of the pipe was solid to prevent infiltration in the upper silt/clay materials. The augers were then removed and the hole was backfilled with gravel to the ground surface to prevent caving of the native, granular material.

The log of the borings, summarizing the materials encountered and the well construction detail, is included in Attachment A as Figures A-1 and A-2.

PERCOLATION TESTING

Percolation tests were performed using the falling-head test method. This method includes filling the polyvinyl chloride (PVC) casing with water and recording the water level drop over regular time intervals.

Prior to performing the actual percolation testing, "pre-soaking" is performed. Pre-soaking consists of filling the PVC casing with water to the ground surface and allowing the water to infiltrate into the soils. Testing is usually performed the day after the pre-soaking. However, if the water added to the hole infiltrates faster than half the initial wetted depth in 30 minutes in four consecutive readings, then testing can be performed the same day.

The depth of the testing in boring B-1 was set at a maximum depth of 35 feet BGS and was intended to evaluate the permeability of the deep fine sand layer. The screened interval was 10 to 35 feet BGS. The depth of the testing in boring B-2 was set at a maximum depth of 20 feet BGS and was intended to evaluate the permeability of the shallow gravelly silt layer. The screened interval was set at 10 to 20 feet BGS.

After completion of the percolation tests, the PVC pipes were removed and the holes were backfilled with native soil to the ground surface.

TESTING METHODOLOGY

Boring B-1

Water was added to the casing in boring B-1 for over one hour. During the hour of attempted pre-soak, the water dissipated into the fine sand strata at the bottom of the casing as quickly as water was introduced. We estimate that over 500 gallons of water was discharged into the hole during that time.

The test was abandoned as it was not possible to make the necessary measurements because the water infiltrated so rapidly. To provide information for design, however, we will provide an estimate of the infiltration rate based on assumed data.

Boring B-2

To start the pre-soak, the hole was filled with clear water to the ground surface and water level readings were taken at time intervals of every 30 minutes. The water level was refilled to the ground surface after each reading. In each of four consecutive readings, the water seeped faster than half the initial wetted depth of 20 feet BGS. As a result of this condition, testing was initiated after the fourth reading (two hours).

We measured and recorded the drop in water level every 10 minutes for a minimum of 60 minutes, refilling the hole to the surface with clear water between each reading. After 60 minutes of consistent readings, defined as having less than 10 percent variance, the water level was allowed to drop to a depth of 11 feet BGS, which is the estimated shallowest design infiltration depth; two additional readings were taken at 10-minute intervals. The water was refilled to a depth of 11 feet BGS between readings.

TEST RESULTS

Table 2 summarizes the result of our percolation tests. Our calculations are presented in Attachment B.

Table 2. Summary of Test Results

Test Location	Test Depth (feet BGS)	Soil Type	mpi		in/hr	
			Average	Lowest value	Average	Lowest value
B-1	10 - 35	SP (fine sand)	5.04*	5.05*	11.92*	11.88*
B-2	10 - 20	ML (gravelly silt)	8.36	9.99	7.23	6.01

* estimated rates
mpi: minutes per inch
in/hr: inches per hour

CONCLUSIONS

Based on the site conditions and the results of our percolation testing, the proposed dry well and trench systems are feasible for stormwater infiltration at the site.

The systems can be designed to discharge water into either the upper gravelly silt strata present at the site between depths of approximately 12 and 20 feet BGS or the fine sand layer present below depths of 25.0 to 26.0 feet BGS using the percolation rates presented in Table 2.

A percolation rate between the average and the most conservative rate is typically selected for use when designing dry well systems, retention basins, or sewage disposal systems. In this case, the average percolation rate is 7.23 in/hr and the most conservative value is 6.01 in/hr.


It should be noted that the percolation rates calculated during our field investigation are based on rates determined during short duration field tests and could vary from actual long-term rates. Also the percolation tests were clear-water tests and infiltration rates could be affected by silt build-up, debris, or other factors that occur at the site in the future.


◆ ◆ ◆

We appreciate the opportunity to be of service to you. Please call if you have questions concerning this report or if we can provide additional services.

Sincerely,

GeoDesign, Inc.


Susan F. Kirkgard, C.E.G.
Associate Geologist




Christopher J. Zadoorian, G.E.
Principal Engineer

SFK:CJZ:kt

Attachments

Two copies submitted

Document ID: SMonica-6-01-071309-geolr.doc

© 2009 GeoDesign, Inc. All rights reserved.

REFERENCES

California Department of Water Resources, 1961 "Planned Utilization of the Ground Water Basins of the Coastal Plain of Los Angeles County, Appendix A, Ground Water Geology," Bulletin No. 104.

California Department of Water Resources, 2008, "On-Line Groundwater Data Library,"
http://wdl.water.ca.gov/gw/hyd/rpt_basin_data4_CF.cfm.

California Geological Survey (formerly California Division of Mines and Geology), 1998, "Seismic Hazard Evaluation of the Beverly Hills 7.5-Minute Quadrangle, Los Angeles County, California," Open-File Report 98-14.

California Geological Survey (formerly California Division of Mines and Geology), 1999, "Seismic Hazard Zones Beverly Hills Quadrangle, Los Angeles County, California," Official Map released March 25, 1999.

Dibblee, T. W., Jr., 1991, "Geologic Map of the Beverly Hills and Van Nuys (South) Quadrangles, California," Dibblee Geological Foundation Map DF-31

Los Angeles, County of, Department of Public Works, 2009, "water Ground Water Wells,"
<http://dpwgis.co.la.ca.us/website/wells>.


Santa Monica, City of, 2001, "City of Santa Monica Geologic Hazards," Information Systems Division, Geographic Information Systems, dated April 2001

Southern California Regional Water Quality Control Board, undated "Frequently Asked Questions, Minimum Lot Size Requirements for Subsurface Disposal Systems," 9 pages.

Printed By: aday | Print Date: 7/13/2009 2:23:29 PM
File Name: \\chromite\files\jobs\5-z\SMonica\SMonica-6-01\Figures\CAD\SMonica-6-01-VN01.dwg | Layout: FIGURE 1



VICINITY MAP BASED ON AERIAL PHOTOGRAPH OBTAINED FROM GOOGLE EARTH PRO®



GEO DESIGN INC
2121 S Towne Centre Place - Suite 130
Anahelm CA 92806
Off 714.634.3701 Fax 714.634.3711


SMONICA-6-01

VICINITY MAP

JULY 2009


CITY TV TENANT IMPROVEMENT PROJECT
SANTA MONICA, CA

FIGURE 1




LEGEND:

- B-1 ⊕ BORING
- PROPERTY LINE



SITE PLAN BASED ON DRAWING PROVIDED BY
CITY OF SANTA MONICA, MAY 18, 2009

SYMBOL	SAMPLING DESCRIPTION
	Location of sample obtained in general accordance with ASTM D 1586 Standard Penetration Test with recovery
	Location of sample obtained using thin-wall Shelby tube or Geoprobe® sampler in general accordance with ASTM D 1587 with recovery
	Location of sample obtained using Dames & Moore sampler and 300-pound hammer or pushed with recovery
	Location of sample obtained using Dames & Moore or 3-inch-O.D. split-spoon sampler and 140-pound hammer or pushed with recovery
	Location of grab sample
	Rock coring interval
	Water level during drilling
	Water level taken on date shown



GEOTECHNICAL TESTING EXPLANATIONS

ATT	Atterberg Limits	P	Pushed Sample
CBR	California Bearing Ratio	PP	Pocket Penetrometer
CON	Consolidation	P200	Percent Passing U.S. Standard No. 200 Sieve
DD	Dry Density	RES	Resilient Modulus
DS	Direct Shear	SIEV	Sieve Gradation
HYD	Hydrometer Gradation	TOR	Torvane
MC	Moisture Content	UC	Unconfined Compressive Strength
MD	Moisture-Density Relationship	VS	Vane Shear
OC	Organic Content	kPa	Kilopascal

ENVIRONMENTAL TESTING EXPLANATIONS


CA	Sample Submitted for Chemical Analysis	ND	Not Detected
P	Pushed Sample	NS	No Visible Sheen
PID	Photoionization Detector Headspace Analysis	SS	Slight Sheen
ppm	Parts per Million	MS	Moderate Sheen
		HS	Heavy Sheen




2121 S Towne Centre Place - Suite 130
 Anaheim CA 92806
 Off 714.634.3701 Fax 714.634.3711

EXPLORATION KEY

TABLE A-1

RELATIVE DENSITY - COARSE-GRAINED SOILS											
Relative Density		Standard Penetration Resistance		Dames & Moore Sampler (140-pound hammer)		Dames & Moore Sampler (300-pound hammer)					
Very Loose		0 - 4		0 - 11		0 - 4					
Loose		4 - 10		11 - 26		4 - 10					
Medium Dense		10 - 30		26 - 74		10 - 30					
Dense		30 - 50		74 - 120		30 - 47					
Very Dense		More than 50		More than 120		More than 47					
CONSISTENCY - FINE-GRAINED SOILS											
Consistency		Standard Penetration Resistance		Dames & Moore Sampler (140-pound hammer)		Dames & Moore Sampler (300-pound hammer)		Unconfined Compressive Strength (tsf)			
Very Soft		Less than 2		Less than 3		Less than 2		Less than 0.25			
Soft		2 - 4		3 - 6		2 - 5		0.25 - 0.50			
Medium Stiff		4 - 8		6 - 12		5 - 9		0.50 - 1.0			
Stiff		8 - 15		12 - 25		9 - 19		1.0 - 2.0			
Very Stiff		15 - 30		25 - 65		19 - 31		2.0 - 4.0			
Hard		More than 30		More than 65		More than 31		More than 4.0			
PRIMARY SOIL DIVISIONS					GROUP SYMBOL		GROUP NAME				
COARSE-GRAINED SOILS (more than 50% retained on No. 200 sieve)	GRAVEL (more than 50% of coarse fraction retained on No. 4 sieve)	CLEAN GRAVELS (< 5% fines)			GW or GP		GRAVEL				
		GRAVEL WITH FINES (≥ 5% and ≤ 12% fines)			GW-GM or GP-GM		GRAVEL with silt				
					GW-GC or GP-GC		GRAVEL with clay				
		GRAVELS WITH FINES (> 12% fines)			GM		silty GRAVEL				
	GC				clayey GRAVEL						
	GC-GM				silty, clayey GRAVEL						
	SAND (50% or more of coarse fraction passing No. 4 sieve)	CLEAN SANDS (<5% fines)			SW or SP		SAND				
		SANDS WITH FINES (≥ 5% and ≤ 12% fines)			SW-SM or SP-SM		SAND with silt				
					SW-SC or SP-SC		SAND with clay				
		SANDS WITH FINES (> 12% fines)			SM		silty SAND				
SC					clayey SAND						
SC-SM					silty, clayey SAND						
FINE-GRAINED SOILS (50% or more passing No. 200 sieve)	SILT AND CLAY	Liquid limit less than 50			ML		SILT				
					CL		CLAY				
					CL-ML		silty CLAY				
					OL		ORGANIC SILT or ORGANIC CLAY				
		Liquid limit 50 or greater			MH		SILT				
					CH		CLAY				
					OH		ORGANIC SILT or ORGANIC CLAY				
					PT		PEAT				
HIGHLY ORGANIC SOILS											
MOISTURE CLASSIFICATION			ADDITIONAL CONSTITUENTS								
Term		Field Test		Secondary granular components or other materials such as organics, man-made debris, etc.							
dry	very low moisture, dry to touch	Percent	Silt and Clay In:				Sand and Gravel In:				
			Fine-Grained Soils		Coarse-Grained Soils		Percent		Fine-Grained Soils		Coarse-Grained Soils
moist	damp, without visible moisture	< 5	trace	trace	< 5	trace	trace	trace	trace		
		5 - 12	minor	with	5 - 15	minor	minor	minor	minor		
wet	visible free water, usually saturated	> 12	some	silty/clayey	15 - 30	with	with	with	with		
		> 30			> 30	sandy/gravelly	sandy/gravelly	sandy/gravelly	sandy/gravelly		
 2121 S Towne Centre Place - Suite 130 Anaheim CA 92806 Off 714.634.3701 Fax 714.634.3711			SOIL CLASSIFICATION SYSTEM					TABLE A-2			

BORING LOG: SMONICA-6-01-B1_2.CPJ GEODESIGN.GDT PRINT DATE: 7/13/09:SMS:KT



DRILLED BY: JDK Drilling, Inc.

LOGGED BY: SFK

COMPLETED: 06/29/09

BORING METHOD: hollow-stem auger (see report text)

BORING BIT DIAMETER: 8-inch



2121 Towne Centre Place - Suite 130
 Anaheim CA 92806
 Off 714.634.3701 Fax 714.634.3711

SMONICA-6-01

BORING B-1

JULY 2009

CITY TV TENANT IMPROVEMENT PROJECT
 SANTA MONICA, CA

FIGURE A-1


BORING LOG: SMONICA-6-01-B1_2.GPJ GEODESIGN.CDT PRINT DATE: 7/13/09:SMS:SKT

DEPTH FEET	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION DEPTH	TESTING	SAMPLE	▲ BLOW COUNT ● MOISTURE CONTENT % ▨ RQD% ▩ CORE REC%	INSTALLATION AND COMMENTS	
30.0		(continued from previous page)				0 50 100		
32.5								
35.0							50/5"	
37.5								Bentonite chips
40.0							50/4"	Soil backfill
42.5								
45.0							50/5"	
47.5								
50.0			Exploration completed at a depth of 49.3 feet. Groundwater not encountered. Exploration backfilled to 35.0 feet at completion of drilling and percolation test performed.	82.2 49.3			50/4"	
52.5								
55.0								
57.5								
60.0						0 50 100		

DRILLED BY: JDK Drilling, Inc. LOGGED BY: SFK COMPLETED: 06/29/09

BORING METHOD: hollow-stem auger (see report text) BORING BIT DIAMETER: 8-inch

<p>2121 Towne Centre Place - Suite 130 Anaheim CA 92806 Off 714.634.3701 Fax 714.634.3711</p>	SMONICA-6-01	BORING B-1 (continued)	
	JULY 2009	CITY TV TENANT IMPROVEMENT PROJECT SANTA MONICA, CA	FIGURE A-1



BORING LOG SMONICA-6-01-B1 - 2.GPJ GEODESIGN.GDT PRINT DATE: 7/13/09 SMS:KT

DRILLED BY: JDK Drilling, Inc. LOGGED BY: SFK COMPLETED: 06/29/09

BORING METHOD: hollow-stem auger (see report text) BORING BIT DIAMETER: 8-inch

<p>2121 Towne Centre Place - Suite 130 Anaheim CA 92806 Off 714.634.3701 Fax 714.634.3711</p>	SMONICA-6-01	BORING B-2	
	JULY 2009	CITY TV TENANT IMPROVEMENT PROJECT SANTA MONICA, CA	FIGURE A-2

DEPTH FEET	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION DEPTH	TESTING	SAMPLE	BLOW COUNT		MOISTURE CONTENT %		INSTALLATION AND COMMENTS
						RQD%	CORE REC%			
30.0		(continued from previous page)								
32.5										
35.0										
37.5										
40.0		Exploration completed at a depth of 40.0 feet.	90.5 40.0							
42.5		Groundwater not encountered. Exploration backfilled to 20.0 feet at completion of drilling and percolation test performed.								
45.0										
47.5										
50.0										
52.5										
55.0										
57.5										
60.0										

BORING LOG: SMONICA-6-01-B1-2.GPJ GEODESIGN.CAD PRINT DATE: 7/13/09 SMS:KT

DRILLED BY: JDK Drilling, Inc.

LOGGED BY: SFK

COMPLETED: 06/29/09

BORING METHOD: hollow-stem auger (see report text)

BORING BIT DIAMETER: 8-inch



2121 Towne Centre Place - Suite 130
Anahelm CA 92806
Off 714.634.3701 Fax 714.634.3711

SMONICA-6-01

BORING B-2
(continued)

JULY 2009

CITY TV TENANT IMPROVEMENT PROJECT
SANTA MONICA, CA

FIGURE A-2

PERCOLATION TEST CALCULATIONS

Boring Number: B-1
 Diameter of Hole: 0.66 foot
 Hours Pre-Soak: 1.00 (unable to sustain water level due to rapid dissipation)
 Time Pre-Soak Initiated: 11:52
 Depth of Bottom (Below Grade): 35.0 feet
 Name of Tester: Susan Kirkgard
 Date Tested: 6/29/2009
 Method to Prevent Caving: Gravel Packing
 Checked by: CJZ
 Gravel Packing Correction Factor: 0.5

pre-soak t-initial	t-final	delta t (hours)	d-bottom (feet)	d-initial	d-final	delta d=F	Lave	D (feet)	Q (gal/s/day)	Corrected Q	mpi	in/hr
11:52	12:07	0.25	35.00	0.00	35.00	35.00	17.50	0.66	47.52	23.76	7.56	7.92
12:07	12:22	0.25	35.00	0.00	35.00	35.00	17.50	0.66	47.52	23.76	7.56	7.92
12:22	12:37	0.25	35.00	0.00	35.00	35.00	17.50	0.66	47.52	23.76	7.56	7.92
12:37	12:52	0.25	35.00	0.00	35.00	35.00	17.50	0.66	47.52	23.76	7.56	7.92

Boring B-1 t-initial	t-final	delta t (hours)	d-bottom (feet)	d-initial	d-final	delta d=F	Lave	D (feet)	Q (gal/s/day)	Corrected Q	mpi	in/hr
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.28	35.64	5.05	11.88
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.57	35.78	5.03	11.93
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.57	35.78	5.03	11.93
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.57	35.78	5.03	11.93
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.57	35.78	5.03	11.93
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.57	35.78	5.03	11.93
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.57	35.78	5.03	11.93
		0.17	35.00	0.00	35.00	35.00	17.50	0.66	71.28	35.64	5.05	11.88
					average	35.00				average	5.04	11.92

PERCOLATION TEST CALCULATIONS

Boring Number: B-2
 Diameter of Hole: 0.66 foot
 Hours Pre-Soak: 2.00
 Time Pre-Soak Initiated: 13:34
 Depth of Bottom (Below Grade): 20.00 feet
 Name of Tester: Susan Kirkgard
 Date Tested: 6/29/2009
 Method to Prevent Caving: Gravel Packing
 Checked by: CJZ
















Gravel Packing Correction Factor 0.5

Date: 7/12/2009

pre-soak	t-initial	t-final	delta t (hours)	d-bottom (feet)	d-initial	d-final	delta d=F	Lave	D (feet)	Q (gal/sf/day)	Corrected Q	mpi	in/hr
	13:34	14:04	0.50	20.00	0.00	20.00	20.00	10.00	0.66	23.76	11.88	15.15	3.96
	14:04	14:34	0.50	20.00	0.00	20.00	20.00	10.00	0.66	23.76	11.88	15.15	3.96
	14:34	15:04	0.50	20.00	0.00	20.00	20.00	10.00	0.66	23.76	11.88	15.15	3.96
	15:04	15:34	0.50	20.00	0.00	16.40	16.40	11.80	0.66	16.51	8.26	21.80	2.75

Boring B-2	t-initial	t-final	delta t (hours)	d-bottom (feet)	d-initial	d-final	delta d=F	Lave	D (feet)	Q (gal/sf/day)	Corrected Q	mpi	in/hr
	15:34	15:44	0.17	20.00	0.00	13.40	13.40	13.30	0.66	36.05	18.03	9.99	6.01
	15:45	15:54	0.17	20.00	0.00	15.40	15.40	12.30	0.66	44.80	22.40	8.04	7.47
	15:55	16:05	0.17	20.00	0.00	15.20	15.20	12.40	0.66	43.86	21.93	8.21	7.31
	16:05	16:15	0.17	20.00	0.00	15.30	15.30	12.35	0.66	44.33	22.17	8.12	7.39
	16:15	16:25	0.17	20.00	0.00	14.40	14.40	12.80	0.66	40.28	20.13	8.94	6.71
	16:25	16:35	0.17	20.00	11.00	17.70	6.70	5.65	0.66	42.43	21.22	8.48	7.07
	16:35	16:45	0.17	20.00	11.00	18.30	7.30	5.35	0.66	48.83	24.41	7.37	8.14
	16:45	16:55	0.17	20.00	11.00	18.10	7.10	5.45	0.66	46.62	23.31	7.72	7.77

average 11.85 average 8.36 average 7.23



REVISIONS BY

BIRBAGROUP

architects

2350 Hyperion Avenue Los Angeles California 90027 (213) 868-9768

PROPOSED BUILDING FOR GERMAN AUTO TECHNIK A.G. 1054 9th STREET, SANTA MONICA

Date


Scale AS NOTED

Drawn


Job 90-20

Sheet


3 of 4 Sheets




ALUM. WINDOW SILL SCALE 3/8" = 1'-0"



ALUM. LOUVER SILL SCALE 3/8" = 1'-0"



DOOR HEAD SCALE 3/8" = 1'-0"



PARAPET SCALE 3/8" = 1'-0"

Certificate of Compliance (Part 2 of 2) Performance Compliance CF-1B

GERMAN AUTO TECHNIK A.G. 2000 For Entertainment Agency Use Only
 CURSH ENGINEERING (415) 826-7345 CURSH ENGINEERING
 10000 Wilshire Blvd. Suite 1000 Los Angeles, CA 90024


Note: More than one Part 2 may be submitted, but all must reference the same Part 1. The person responsible for design compliance for each major building system shall prepare the following compliance statement by signing the appropriate space below.

Envelope	Allowed	Proposed	Standard of Improvement
1. Average Roof Ceiling U-value	0.10	0.10	AS-1000
2. Average Exterior Wall U-value	0.10	0.10	AS-1000
3. Average Window U-value	0.30	0.30	AS-1000
4. Glazing Area in Wall	30%	30%	AS-1000
5. Average SC (Wall)	0.75	0.75	AS-1000
6. Glazing Area in Roof	10%	10%	AS-1000
7. Average SC (Roof)	0.15	0.15	AS-1000


Lighting	Allowed	Proposed	Standard of Improvement
8. Ratio of Allowed LFD	1.60	1.60	AS-1000
9. LFD	1.60	1.60	AS-1000
10. Package Lighting Reduction	10%	10%	AS-1000
11. Adjusted LFD	1.60	1.60	AS-1000
12. Lighting Control Credits	0%	0%	AS-1000

Mechanical	Allowed	Proposed	Standard of Improvement
13. Rated Cooling Efficiency	9.00	9.00	AS-1000
14. Rated Cooling Capacity	18.00	18.00	AS-1000
15. Rated Heating Efficiency	3.00	3.00	AS-1000
16. Rated Heating Capacity	18.00	18.00	AS-1000
17. Economizer cooling	N	N	AS-1000
18. Economizer heating	N	N	AS-1000


UNIT FAN POWER = (1.85 WATTS/CFM) WS-4A
 (550 CFM) (200 FT²)
 = 309 WATTS/CFM




ALUMINUM WINDOW HEAD SCALE 3/8" = 1'-0"




ALUMINUM LOUVER HEAD SCALE 3/8" = 1'-0"




ALUMINUM WINDOW JAMB SCALE 3/8" = 1'-0"



ALUMINUM LOUVER JAMB SCALE 3/8" = 1'-0"



DOOR JAMB SCALE 3/8" = 1'-0"



COMPLIES WITH TABLE A3-B
 1985 UBCS 1987 SUPPLEMENT ITEM NO. 67
 1988 UBC ITEM NO. 16-13
 COMPLIES WITH FIRE RESISTANCE
 DESIGN MANUAL CH. 10, TABLE NO. 10-100

REVISIONS

1	
2	
3	
4	
5	
6	
7	
8	
9	
10	

DATE: 9-20-20









Scale: AS NOTED

Job: 90-20



Sheet: 4 of 4

PROPOSED BUILDING FOR
 GERMAN AUTO TECHNIK A.G.
 1084 19TH STREET, SANTA MONICA

BIRBA GROUP
 ARCHITECTS
 2350 Hyattman Avenue Los Angeles California 90027
 (213) 606-9766



WALL THICKNESS	VERTICAL REINF.	HORIZ. REINF.	CHAS.
0"	14 @ 32"	14 @ 32"	SINGLE
MASONRY	15 @ 32"	14 @ 32"	SINGLE
0"	14 @ 16"	14 @ 16"	SINGLE
CONCRETE	14 @ 16"	14 @ 16"	SINGLE



CONCRETE BLOCK MASONRY

- CONCRETE BLOCK WALLS SHALL BE CONSTRUCTED OF 1600-WEIGHT GRADE "M" UNITS CONFORMING TO ASTM C90.
- UNITS SHALL BE SUFFICIENTLY MOIST AT TIME OF LAYING TO PREVENT DRYING OF ADJACENT AND EXPOSED SURFACES WHICH MIGHT DRAW MOISTURE FROM JOINTS TO MORTAR AND GROUT.
- MORTAR SHALL BE MACHINE MIXED TYPE "S" CONSISTING OF, BY VOLUME, 1 PART CEMENT, 1/4 PART LIME PUTTY AND 2 PARTS SAND. GROUT SPACES MORE THAN 4 IN. WIDE MAY HAVE NOT MORE THAN 2 PARTS FEA GRAVEL ADDED TO COMPONENTS DESCRIBED ABOVE.
- GROUT FOR MORTAR & GROUT SHALL BE LOW ALKALI TYPE I OR II CONFORMING TO ASTM C 150.
- MORTAR AND GROUT SHALL HAVE THE FOLLOWING 28 DAY STRENGTH:
 - MORTAR - 1800 PSI
 - GROUT - 2000 PSI
- ALL WALLS SHALL BE BUILT SOLID, I.E. NO MAXIMUM GROUT LIFT SHALL EXCEED 4 FT. SEE ARCH DRAWINGS FOR BLOCK SIZE, COLOR, TEXTURE, BONDING PATTERN AND JOINTING.
- CONTINUOUS INSPECTION IS REQUIRED FOR ALL CONCRETE BLOCK WALLS.

CONCRETE

- CONCRETE USED IN THE WORK SHALL HAVE AN ULTIMATE COMPRESSIVE STRENGTH OF 2000 PSI AT AGE 28 DAYS.
- ALL CONCRETE SHALL BE STORE CONCRETE UTILIZING AGGREGATE CONFORMING TO ASTM C 637.
- CEMENT SHALL BE TYPE I OR II CONFORMING TO ASTM C 150.
- CONCRETE COVER OVER REINFORCING STEEL SHALL BE AS FOLLOWS:
 - A. CONCRETE AGAINST EARTH (UNFORMED) - 2"
 - B. CONCRETE AGAINST EARTH (FORMED) - 1 1/2"
- BEFORE CONCRETE IS PLACED THE CONTRACTOR SHALL COORDINATE AND CHECK WITH ALL TRADES TO ENSURE THE PROPER PLACEMENT OF ALL SPINDERS, SLEEVES, FASTENERS, CURBS, DEPRESSIONS, ETC. RELATING TO THE WORK.
- SLEEVES, OPENINGS OR OTHER ATTACHMENTS NOT SHOWN ON THE DRAWINGS SHALL BE APPROVED BY THE STRUCTURAL ENGINEER & THE LOCAL BUILDING AGENCY PRIOR TO PLACING OF CONCRETE.
- CONTINUOUS INSPECTION NOT REQUIRED FOR CONCRETE.

REINFORCING STEEL

- ALL REINFORCING STEEL SHALL BE NEW STOCK DEFORMED BARS CONFORMING TO ASTM A615 AS FOLLOWS:
 - A. STIRRUPS & TIES - GRADE 40
 - B. STEEL IN MASONRY WALLS - GRADE 40 W.R.O.
 - C. ALL OTHER - GRADE 60
 - D. WALL PANELS TO FOOTINGS - GRADE 40
- WELDED WIRE FABRIC SHALL BE MADE OF COLD DRAWN WIRE & SHALL CONFORM TO ASTM A 185.
- ALL BAR BENDS SHALL BE MADE COLD.
- BAR LAPS SHALL BE MADE AWAY FROM POINTS OF MAXIMUM STRESS OR AT LOCATIONS SHOWN ON THE DRAWINGS AND AS INDICATED BELOW. THE MAXIMUM AMOUNT OF ANY LAP SHALL BE 2 FEET.
 - A. COLUMNS - 24 DIAMETERS
 - B. HORIZONTAL STEEL IN CONCRETE SLABS, WALLS, BEAMS AND GIRDS - 36 DIAMETERS
 - C. CONCRETE BLOCK MASONRY - 40 DIAMETERS
- ALL TESTING OF REINFORCING STEEL SHALL BE AS REQUIRED BY LOCAL BUILDING CODE OR AS OTHERWISE NOTED IN THE SPECIFICATIONS.
- PRIOR WELDING PROCEDURE APPROVAL IS REQUIRED FOR WELDING OF GRADE 60 REINFORCING STEEL. PROCEDURE TO INCLUDE PREHEATING TEMPERATURE AND LENGTH OF PREHEATING INDIVIDUAL PIECES OF REINFORCING STEEL PER AISC 3.77.
- ALL FIELD WELDING SHALL BE DONE UNDER CONTINUOUS INSPECTION OF A REGISTERED DEPUTY INSPECTOR LICENSED BY THE LOCAL BUILDING OFFICIAL.

WELDING OF REINFORCING STEEL

FIELD WELDING OF REINFORCING STEEL SHALL BE PERFORMED BY WELDERS SPECIFICALLY CERTIFIED FOR REINFORCING STEEL. PRIOR TO WELDING THE CARBON EQUIVALENT (CE) OF STEEL SHALL BE DETERMINED. REINFORCING STEEL WHOSE "CE" CANNOT BE IDENTIFIED OR WHOSE "CE" EXCEEDS 0.75% SHALL NOT BE WELDED. EXCEPT FOR REINFORCING STEEL CONFORMING TO ASTM A 706, REINFORCING STEEL SHALL BE PREHEATED AS SHOWN IN TABLE 1, PER AISC 3.77. IN ADDITION, STEEL WITH "CE" BETWEEN 0.65% AND 0.75% SHALL BE WELDED ONLY WHEN PRIOR QUALIFICATION TESTS VERIFY ACCEPTABLE WELDABILITY.

STRUCTURAL STEEL

- STRUCTURAL STEEL ROLLED SECTIONS & PLATE USED IN THE WORK SHALL CONFORM TO ASTM A36.
- PIPE COLUMNS SHALL BE WELDED SEAMLESS PIPE CONFORMING TO ASTM A53 FOR GRADE "B" PIPE.
- SQUARE OR RECTANGULAR TUBES SHALL BE WELDED SEAMLESS SECTIONS MADE OF STEEL CONFORMING TO ASTM A500.
- ALL FABRICATION SHALL BE DONE IN THE SHOP OF A FABRICATOR LICENSED BY THE CITY OF LOS ANGELES OR UNDER THE CONTINUOUS INSPECTION OF A REGISTERED DEPUTY INSPECTOR LICENSED BY THE SAME BODY.
- ALL STRUCTURAL STEEL EXCEPT THAT PORTION TO BE EMBEDDED IN CONCRETE OR TO RECEIVE SPRAYED-ON FIREPROOFING SHALL RECEIVE ONE SHOP COAT OF PAINT AS DESCRIBED IN THE SPECIFICATIONS.
- SHOP DRAWINGS SHALL BE SUBMITTED TO THE ARCHITECT AND STRUCTURAL ENGINEER FOR APPROVAL PRIOR TO FABRICATION. ANY FABRICATION DONE PRIOR TO RECEIPT OF APPROVED SHOP DRAWINGS SHALL BE DONE AT THE CONTRACTOR'S OWN RISK.
- BOLTED CONNECTIONS USED IN THE WORK SHALL CONSIST OF UNFINISHED BOLTS CONFORMING TO ASTM A307. BOLTS SHALL BE 3/4" UNLESS OTHERWISE NOTED.
- CONTRACTOR SHALL PROVIDE BRACING AS REQUIRED TO MAINTAIN THE ALIGNMENT OF THE BUILDING FRAME UNTIL ALL WELDING IS COMPLETED AND/OR SLABS AND WALLS ARE POURED.

GENERAL

- THE CONTRACTOR SHALL EXAMINE THE STRUCTURAL DRAWINGS AND SHALL NOTIFY THE STRUCTURAL ENGINEER OF ANY DISCREPANCIES HE MAY FIND BEFORE PROCEEDING WITH THE WORK.
- THE CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS AT THE SITE AND SHALL NOTIFY STRUCTURAL ENGINEER OF DISCREPANCIES BETWEEN THE ACTUAL CONDITIONS AND INFORMATION SHOWN ON THE DRAWINGS BEFORE PROCEEDING WITH THE WORK.
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE STRUCTURAL ENGINEER OF ANY CONDITION WHICH, IN HIS OPINION, MIGHT ENDANGER THE STABILITY OF THE STRUCTURE OR CAUSE DISTRESS TO THE STRUCTURE.
- ALL WORK SHALL CONFORM TO THE MINIMUM STANDARDS OF THE 1989 EDITION OF THE CALIFORNIA BUILDING CODE AS SUCH, OTHER REGULATING AGENCIES EXERCISING AUTHORITY OVER ANY PORTION OF THE WORK INCLUDING THE STATE OF CALIFORNIA, DIVISION OF OCCUPANCY SAFETY.
- ALL WORK SHALL CONFORM TO THE BEST PRACTICE PREVAILING IN THE VARIOUS TRADES COMPRISING THE WORK.
- ALL ASTM DESIGNATIONS SHALL BE AS REFERRED TO DATE.
- SPECIFIC NOTES & DETAILS SHALL TAKE PRECEDENCE OVER GENERAL NOTES & SPECIFICATIONS.
- THE CONTRACTOR SHALL REFER TO THE SPECIFICATIONS FOR INFORMATION NOT COVERED BY THESE GENERAL NOTES ON THE STRUCTURAL DRAWINGS.
- THE CONTRACTOR SHALL PROVIDE TEMPORARY ERECTION BRACING & SHORING FOR ALL STRUCTURAL MEMBERS ON AS REQUIRED FOR STRUCTURAL STABILITY OF THE STRUCTURE THROUGH ALL PHASES OF CONSTRUCTION.
- THE CONTRACTOR SHALL TAKE ALL STEPS NECESSARY TO PROTECT THE PREEXISTING STRUCTURE AFTER THE INSTALLATION OF ALL STRUCTURAL AND FINISH MATERIALS.
- CONTRACTOR SHALL NOTIFY ADJACENT PROPERTY OWNERS IN WRITING OF HIS INTENTIONS TO START THE WORK, AND THAT AN EXCAVATION WILL BE MADE, A MINIMUM OF 10 FEET BEFORE THE START OF WORK SO THAT ADJACENT OWNERS MAY PROTECT THEIR PROPERTY.

WOOD FRAMING

ALL LUMBER SHALL BE STRESS GRADE DOUGLAS FIR/LARCH UNLESS OTHERWISE NOTED.

- 2x4 & 2x6 STUDS - 1000 PSI
- ROOF JOISTS AND 2x6 STUDS - D.F. NO. 2 S.P.F.
- FLOOR JOISTS - D.F. NO. 2 S.P.F.
- ALL BEAMS LESS THAN 5" THICK - S.P.F. NO. 1 S.P.F.
- BEAMS GREATER THAN 5" THICK - S.P.F. NO. 1 S.P.F.
- POSTS - S.P.F. NO. 1 S.P.F.

- ALL WOOD IN DIRECT CONTACT WITH THE GROUND, MASONRY OR CONCRETE SHALL BE TREATED WITH A PRESERVATIVE OR SHALL BE DECAY RESISTANT WOOD AS PRESCRIBED IN THE UNIFORM BUILDING CODE.
- ALL WALLS SHALL BE BOLTED TO FOUNDATION (CONCRETE OR CONCRETE BLOCK) WITH 1/2" X 8" ANCHOR BOLTS AT 16" O.C. OF EACH END. WALLS SHALL BE BOLTED TO FOUNDATION AT 16" O.C. 7/32" X 8" SHOT-PINS AT 16" O.C. EXCEPT AS CALLED OUT FOR SHEAR WALLS. SHOT-PINS SHALL BE HELD STRAIGHT OR HELD IN PLACE BY BARZELLS.
- ALL HARDWARE USED IN THE WORK SHALL BE SIMON STEINER FILE OR OTHER HARDWARE OF EQUAL CAPACITY AND HAVING LSC APPROVAL.
- A DOUBLE PLATE MADE OF TWO MEMBERS OF THE SAME WIDTH AS THE STUDS SHALL BE PLACED AT THE TOP OF EVERY BEARING PARTITION OR EXTERIOR WALL TO BE BOLTED TO STUDS. STUDS SHALL LAP AT CORNER AND JOINTS IN UPPER AND LOWER MEMBERS SHALL BE STAGGERED EXCEPT AT CORNERS.
- EXTERIOR WALLS AND BEARING PARTITIONS SHALL BE FRAMED OF 2x4 STUDS BY 16" O.C. AND SUPPORTING LOADS FROM ROOF AND A MAXIMUM OF ONE FLOOR ABOVE.
- EVERY WOOD STUD BEARING WALL OR BEARING PARTITION SHALL BE BRACED AT EACH END AS NEAR THERE TO AS POSSIBLE AND AT LEAST EVERY 25 FT. OF ITS LENGTH. THE TYPE OF BRACING SHALL MEET THE CODE REQUIREMENTS FOR THIS PURPOSE.
- FLOOR JOISTS SHALL BE DOUBLED UNDER PARTITIONS RUNNING PARALLEL TO THE JOISTS. FIRST DOUBLED STUDS OR 4x4 POSTS UNDER DOUBLED JOISTS OR 4x4 BEAMS UNLESS OTHERWISE CALLED FOR ON FRAMING PLANS.
- ALL FRAMING SHALL BE DONE IN ACCORDANCE WITH THE MINIMUM REQUIREMENTS OF THE LOCAL BUILDING CODE, EXCEPT AS OTHERWISE SHOWN, AND SHALL BE DONE WITH MINIMUM WIRE NAILS UNLESS OTHER TYPE OF NAIL IS ALLOWED BY THE LOCAL BUILDING CODE (SEE ALSO GENERAL NOTES).
- BOARDS SHALL BE UNFINISHED BOARDS CONFORMING TO ASTM A307.
- PLYWOOD SHALL BE INTERIOR TYPE WITH EXTERIOR GRADE CONFORMING TO PER 1-14 OF SPAN CALLED FOR BELOW. LAID WITH FACE GRAIN PERPENDICULAR TO SUPPORTS. USE COMMON NAILS ONLY UNLESS OTHERWISE APPROVED BY THE STRUCTURAL ENGINEER & LOCAL BUILDING OFFICIAL.
 - A. ROOF SHEATHING SHALL BE 5/8" T & E PLYWOOD, CIV OR BETTER, NAILED WITH 10d NAILS AT 6" O.C. AT ALL DIAPHRAGM AND WALL BOUNDARIES. CONTINUOUS PANEL EDGES ARE NOT ALLOWED. AT 12" O.C. AT WOOD PANEL EDGES AND 16" NAILS AT 12" O.C. TO INTERMEDIATE SUPPORTS. INDEX #32/16.
 - B. FLOOR SHEATHING SHALL BE 5/8" PLYWOOD, CIV OR BETTER, NAILED WITH 10d NAILS AT 6" O.C. AT DIAPHRAGM AND WALL BOUNDARIES. CONTINUOUS PANEL EDGES ARE NOT ALLOWED. AT 12" O.C. AT WOOD PANEL EDGES AND 16" NAILS AT 12" O.C. TO INTERMEDIATE SUPPORTS. INDEX #32/16.
 - C. PLYWOOD SHEATHING SHALL BE INSPECTED AND APPROVED BY BUILDING INSPECTOR BEFORE COVERING WITH FLOOR OR ROOF MATERIAL.
 - D. SOLID BLOCKING AT EDGES REQUIRED FOR PLYWOOD ONLY WHERE CALLED FOR ON DRAWINGS.
 - E. USE SCREW TYPE NAILS AND GLUE FOR FASTENING SHEATHING FOR ALL FLOORS.
- PLYWOOD FOR SHEAR WALLS SHALL BE STRUCTURAL OR CIV AS CALLED FOR ON THE DRAWINGS. ALL PLYWOOD EDGES SHALL BE BLOCKED. PLYWOOD SHALL EXTEND FROM BOTTOM OF LUMBER PLATE TO TOP OF TOPMOST PLATE UNLESS OTHERWISE SHOWN OR AS APPROVED BY STRUCTURAL ENGINEER.

WELDING



















- ALL WELDING SHALL BE PERFORMED BY WELDERS HOLDING CURRENT CERTIFICATION FROM THE CITY OF LOS ANGELES.
- ALL WELDING SHALL BE PERFORMED USING THE ELECTRIC ARC PROCESS IN ACCORDANCE WITH APPLICABLE PORTIONS OF THE "CODE FOR ARC AND TIG WELDING IN BUILDING CONSTRUCTION" OF THE AMERICAN WELDING SOCIETY.
- CONTINUOUS INSPECTION IS REQUIRED FOR FIELD WELDING OF STRUCTURAL AND REINFORCING STEEL.
- ELECTRODES SHALL BE E TO XX.

DRILLED PILES

- DRILLED PILES SHALL BE 24 INCH DIAMETER AT LEAST AND SHALL BE PERFORMED AS SHOWN ON THE DRAWINGS. PILES SHALL PENETRATE A MINIMUM OF 10 FEET BELOW THE BOTTOM OF UNFINISHED EXISTING FLOOR SLABS.
- PILE EXCAVATIONS SHALL BE OBSERVED BY THE FOUNDATION ENGINEER AND SHALL POST A NOTICE AT THE SITE INDICATING THAT THE WORK HAS BEEN PERFORMED ACCORDING TO THE DRAWINGS AND TO HIS SATISFACTION.
- CONCRETE FOR PILES SHALL HAVE A 28 DAY COMPRESSIVE STRENGTH OF 2000 PSI. CONCRETE FOR PILES SHALL BE PLACED UNDER THE CONTINUOUS INSPECTION OF A REGISTERED DEPUTY INSPECTOR LICENSED BY THE CITY OF LOS ANGELES.
- PILE EXCAVATIONS SHALL BE POURED AS SHOWN AND SHALL BE WELDED. PILES SHALL NOT BE LEFT OVERNIGHT.

GERMAN AUTOTECHNIKA
 1511 STREET, SANTA MONICA
 CIVIL & ASSOCIATES
 S-1

REVISIONS	BY




PROPOSED BUILDING FOR:
GERMAN AUTO TECHNIK A.G.
 19th STREET, SANTA MONICA

enVaras&associates
 ARCHITECTURAL ENGINEERS
 1000 WILSON BLVD
 SANTA MONICA, CALIF. 90401
 DATE: 12-6-91
 SCALE: N.T.S.
 DRAWING: 4.P.C.
 NO: 151
S-2
 OF 5 SHEETS


REVISIONS	BY

PROPOSED BUILDING FOR:
GERMAN AUTO TECHNIK A.G.
 19th STREET, SANTA MONICA


er Varas & associates
 ARCHITECTS
 1900 AVENUE OF THE STARS
 SUITE 200
 WASHINGTON, D.C. 20006
 DATE: 4-26-91
 SCALE: 1/4" = 1'-0"
 DRAWN: MFC
 JOB: 75
 SHEET: S-3




1




2




3




4




5




6




7




8




9




10




11




12



13




14




15




16




17




18



19



20



ROOF FRAMING PLAN

PLYWOOD DIAPHRAGM	
①	PLYWOOD CDX W/10' @ 1/2", 4'10" BLK'D
②	PLYWOOD CDX W/10' @ 4'6", 10' BLK'D
③	PLYWOOD CDX W/10' @ 6', 12' BLK'D


REVISIONS	BY

PROPOSED BUILDING FOR:
 GERMAN AUTO TECHNIK A.G.
 1911 STREET, SANTA MONICA

el Varas & associates
 ARCHITECTS

Date 4-26-91
 Scale 1/4" = 1'-0"
 Drawn MPC
 Job 751


Sheet
9-5
 Of 5 Sheets



CONTRACTOR TO INSTALL ONE W.C.S. #HV-7 TENSIO-METER, ONE W.C.S. #COS-HV OVERRIDE CONTROL AND ONE W.C.S. 910 ROUND PALSTIC BOX FOR EVERY STATION USED ON PROJECT. ALSO INSTALL ONE W.C.S. CENTRAL OVERRIDE CONTROL AT AUTOMATIC CONTROLLER. CONTRACTOR TO CONSULT WITH WATER CONSERVATION SYSTEMS INC., PHONE (714) 621-5805 FOR INFORMATION ON TYPE OF EQUIPMENT TO BE USED AND PROPER PLACEMENT THEREOF. IT IS OF UTMOST IMPORTANCE THAT TENSIO-METERS ARE MATCHED WITH EXISTING TYPE OF SOIL.

1 1/2
10

19TH STREET



19TH STREET

ALL LANDSCAPE AND IRRIGATION INSTALLATION SHALL CONFORM TO CITY OF SANTA MONICA MUNICIPAL CODES REGARDING WATER CONSERVATION.

1. AUTOMATIC CONTROLLERS WILL BE PROGRAMMED TO WATER BETWEEN 5:00pm and 10:00 am.
2. ALL LANDSCAPED AREAS SHALL BE PERMANENTLY MAINTAINED AND KEPT FREE OF WEEDS, DEBRIS AND LITTER. ALL PLANT MATERIALS SHALL BE MAINTAINED IN A HEALTHY GROWING CONDITION AND DISEASED OR DEAD PLANT MATERIALS SHALL BE REPLACED IN KIND, PURSUANT TO THE APPROVED PLAN WITHIN 30 DAYS.
3. IF, AT THE TIME OF APPLICATION FOR CERTIFICATE OF OCCUPANCY, OR FINAL BUILDING PERMIT INSPECTION, THE REQUIRED LANDSCAPING IS NOT YET IN PLACE, THE OWNER SHALL FILE WITH THE CITY A DEFERRAL COMPLETION AGREEMENT SECURED IN A MANNER ACCEPTABLE TO THE CITY IN THE SUM OF FOUR DOLLARS (\$4.00) PER SQUARE FOOT OF REQUIRED LANDSCAPING NOT YET IN PLACE TO ENSURE THAT SUCH REQUIRED LANDSCAPING SHALL BE INSTALLED.

SPECIFICATIONS

1. THE CONTRACTOR SHALL ESTABLISH NECESSARY PRECAUTIONS TO PREVENT INJURY TO PROPERTY, UTILITIES, PERSONS, AND THE LIKE ON OR ABOUT THE SITE DURING THE COURSE OF HIS OPERATION.
2. THE LOCATION OF ALL UNDERGROUND SERVICES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF PLANTING OPERATIONS.
3. ALL WORKMANSHIP SHALL BE ACCOMPLISHED IN A MANNER SERVING THE HIGHEST STANDARDS OF THE NURSERY AND LANDSCAPE CONTRACTING TRADE.
4. NO WORK SHALL BE ACCOMPLISHED THAT DOES NOT SERVE THE BEST INTEREST OF THE OWNER.
5. ALL FURNISHED PLANTS AND TREES SHALL MEET A MINIMUM CALIBER #1 GRADE PER GRADES AND STANDARDS FOR NURSERY STOCK, PARTS 1 & 11, CALIFORNIA DEPARTMENT OF AGRICULTURE.
6. ALL SHADES TREES SHALL BE APPROPRIATELY CUTTED AND STAKED AGAINST WIND MOVEMENT.
7. GROUND COVER PLANTING SHALL BE CONTINUOUS UNDER ALL TREE AND SHRUB CANOPIES AS SHOWN ON PLAN.
8. ALL PLANTING BEDS TO RECEIVE 2" DEPTH OF DARK MULCH.
9. ALL FREE STANDING TREES SHALL BE SET IN AN 8" HIGH, 4" DIAMETER MULCHED WATER RETENTION DISH.

10. ALL FURNISHED PLANT MATERIALS AND SOIL SHALL BE GUARANTEED AGAINST DETRIORATION OR LOSS FOR A PERIOD OF 90 CALENDAR DAYS FROM THE DATE OF COMPLETION AND ACCEPTANCE FOR REASONS OTHER THAN THOSE BEYOND HIS CONTROL.
11. ALL GIVEN QUANTITIES SHALL BE VERIFIED BY THE CONTRACTOR PURSUANT TO SUBMISSION OF BID.
12. EXISTING AND PROPOSED SITE CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR PURSUANT TO SUBMISSION OF BID.
13. ANY AND ALL CONTINGENCIES SHALL BE BROUGHT TO THE ATTENTION OF THE GENERAL CONTRACTOR FOR RESOLUTION.
14. ADDITIONAL TERMS AND CONDITIONS SHALL BE PROVIDED FOR IN THE LANDSCAPE CONTRACT AGREEMENT.
15. SUBSTITUTIONS SHALL NOT BE ALLOWED. RECOMMENDATIONS MAY BE FORWARDED TO THE GENERAL CONTRACTOR FOR CONSIDERATION FOR REASONS OF AVAILABILITY OR SITE CONDITIONS.
16. THE GENERAL CONTRACTOR SHALL DEFINE THE LANDSCAPE CONTRACTOR'S GRADING RESPONSIBILITIES.
17. THE LANDSCAPE CONTRACTOR SHALL PROVIDE UNIT SOFT COSTS FOR NECESSARY SOIL PATCHING NOT SPECIFICALLY DEPICTED HEREIN.
18. TWO (2) COPIES OF SOIL TESTS PERFORMED BY AN APPROVED AGRONOMIC SOILS TESTING LABORATORY SHALL BE SUBMITTED WITH PLANS. RECOMMENDED AMENDMENTS TO SOIL AS REQUIRED FOR OPTIMUM PLANT GROWTH SHALL BE INDICATED.

IRRIGATION LEGEND

SYMBOL	1/4" 1/2" MANUFACTURER NUMBER	MODEL NUMBER	DESCRIPTION	GALLONS PER MINUTE	1/4" 1/2" FULL RADIUS EST
▽		1912	POP-UP SPRINKLER 1/8" FLAT SERIES NOZZLE .31" G.S. 1.30" G.P.		
⊖		PVB-150	PRESSURE VACUUM BREAKER/BACKFLOW PREVENTER - INSTALL PER LOCAL CODE		
⊖		100-EFA-CP	ELECTRIC REMOTE CONTROL VALVE		
⊖		125-EFA-CP	ELECTRIC REMOTE CONTROL VALVE		
⊖		150-EFA-CP	ELECTRIC REMOTE CONTROL VALVE		
⊖		33K	QUICK COUPLER AND HOSE KEY		
⊖		RCH-4	PEDISTAL MOUNT CONTROLLER - CONTRACTOR TO VERIFY EXACT LOCATION IN FIELD		
⊖			GATE VALVE - SIZE PER LINE		
⊖			CLASS 315 CHARGED IRRIGATION LINE		
⊖			CLASS 200 LATERAL IRRIGATION LINE - SIZE AS INDICATED		
⊖			SCHED. 40 IRRIGATION SLEEVE - 2" OR LATERAL OR CHARGED LINE WITHIN FIELD		
⊖			P.O.C. POINT OF CONNECTION - CONTRACTOR TO VERIFY IN FIELD		
⊖			H.V.7 SCUP STATE TENSIO-METER (ONE PER CONTROLLER STATION)		
⊖			VALVE NUMBER		
⊖			VALVE SIZE		
⊖			GALLONS PER MINUTE		

IRRIGATION NOTES

DO NOT WILLFULLY INSTALL THE SYSTEM AS DESIGNED, WHEN IT IS OBVIOUS THAT OBSTRUCTIONS OR GRADE DIFFERENCES EXIST THAT WERE NOT KNOWN DURING DESIGNING. SUCH CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER'S AUTHORIZED REPRESENTATIVE, OTHERWISE, THE IRRIGATION CONTRACTOR MUST ASSUME FULL RESPONSIBILITY FOR ANY REVISIONS NECESSARY.

THIS DESIGN IS DIAGNOSTIC. EQUIPMENT SHOWN IN PAVED AREAS IS FOR CLARIFICATION ONLY, AND IS TO BE INSTALLED IN PLANTING AREA WHENEVER POSSIBLE.

UNLESS OTHERWISE NOTED, 120 VOLT ELECTRICAL POWER FOR CONTROLLER(S) TO BE PROVIDED BY OTHER. THE IRRIGATION CONTRACTOR WILL MAKE FINAL ELECTRICAL CONNECTION TO AUTOMATIC CONTROLLER(S) FROM OUTLET PROVIDED BY OTHER.

ALL WIRES FROM CONTROLLER TO AUTOMATIC VALVES TO BE COPPER, DIRECT BURIAL, MIN. #14 GAUGE. INSTALL IN SAME TRENCH AS MAINLINE PIPING WHERE POSSIBLE. MIN. COVERAGE OVER WIRE TO BE 18". COMMON WIRE TO BE WHITE IN COLOR. CONTROL WIRE TO BE DIFFERENT COLOR FOR EACH CONTROLLER USED. BUNDLE AND TAPE WIRES TOGETHER MIN. 2' ON CENTER.

FINAL LOCATION FOR BACKFLOW PREVENTER(S) AND CONTROLLER(S) TO BE DETERMINED BY OWNER'S AUTHORIZED REPRESENTATIVE.

INSTALL EQUIPMENT AS PER DETAILS.

PROVIDE MIN. 18" COVERAGE OVER ALL PRESSURE LINES, AND MIN. 12" COVERAGE OVER ALL NON-PRESSURE LINES. ALL PIPING UNDER PAVING TO BE MIN. SCHEDULE 40 P.V.C. AND TO HAVE MIN. 24" COVER OVER PIPING.

IRRIGATION CONTRACTOR TO FLUSH ALL LINES AND ADJUST ALL HEADS FOR MAXIMUM PERFORMANCE, AND TO PREVENT EXCESSIVE OVERSTRAIGHT ONTO WALKS, DRIVES, BUILDINGS AS MUCH AS POSSIBLE. THIS SHALL INCLUDE SELECTING THE BEST DEGREE OF ARC TO FIT ACTUAL SITE CONDITIONS.

ALL SHRUBBERY HEADS ADJACENT TO PARKING LOT OR ALONG WALKS OR ROADS WILL BE INSTALLED WITH HIGH POP-UP BODIES.

IRRIGATION CONTRACTOR WILL INSTALL SWING CHECK VALVES OR SPRING LOADED CHECK VALVES AS REQUIRED TO ELIMINATE EXCESSIVE DRAINAGE FROM LOW SPRINKLERS. THIS WILL BE IN ADDITION TO ANY CHECK VALVES SHOWN ON PLAN.

ALL P.V.C. MAINLINE FITTINGS TO BE "LONG SOCKET" TYPE AS MANUFACTURED BY DORA COMPANY.

UPON COMPLETION, IRRIGATION CONTRACTOR TO SUPPLY TO OWNER, A COMPLETE SET OF REPRODUCIBLE "AS BUILT" DRAWINGS. DRAWINGS WILL SHOW LOCATION OF ALL VALVES, CROSSING, QUICK COUPLING VALVES, ETC. EACH CONTROLLER TO HAVE ITS OWN CONTROLLER CHART. CHART WILL CLEARLY SHOW EACH AREA SPRINKLED IN A DIFFERENT COLOR AND WILL BE LAMINATED BETWEEN 2 LAYERS OF 10 MIL CLEAR PLASTIC.

THE IRRIGATION SYSTEM SHALL BE FULLY GUARANTEED FOR A PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE BY OWNER. ANY DEFECTIVE MATERIALS OR POOR WORKMANSHIP SHALL BE REPLACED OR CORRECTED BY IRRIGATION CONTRACTOR AT NO COST TO THE OWNER.

PLANT LEGEND

*PLANT QUANTITIES ARE FOR CONTRACTORS CONVENIENCE ONLY. CONTRACTOR IS RESPONSIBLE TO VERIFY ALL PLANT COUNTS.

SYMBOL	BOTANICAL NAME	COMMON NAME	QTY.	SIZE	COMMENTS
○	SHRUBS HEMEROCALLIS HYBRID 'YELLOW'	DAYLILY	74	1" GAL	
○	RAPHIOLEPIS INDICA 'PINK LADY'	INDIA HAWTHORN	21	5 GAL	
■	GROUND COVER GAZANIA 'MITSUWA YELLOW'	TRAILING GAZANIA	TO COVER 360SF FLATS	12" O.C. Δ SP.	

[Handwritten Signature]

REVISIONS	BY

SANTA MONICA AUTO REPAIR
IRRIGATION & PLANTING PLAN




3822 Curson Drive, Suite 130
Newport Beach, CA 92660
Lynn Capovilla, Inc.
Landscape Architects
Lynn Capovilla
Call: 949-423-1414 (714) 758-0150

DRAWN
K.V.
CHECKED
DATE
SCALE
1/4" = 1'-0"
JOB NO.
SHEET
L-1
OF SHEETS

GENERAL REQUIREMENTS

1. Edison and City to inspect all conduits (need 48 hour notice)
2. 30" Minimum cover over conduits
3. SCH 40 PVC on straight runs
4. SCH 80 PVC on sweeps
5. 1/2" pull rope to be installed
6. Contact City for alley or sidewalk crossing requirements

Where conduits are picked up, contractor to mandrel and install pull rope from terminal to terminal.




Not to Scale

GENERAL REQUIREMENTS		MATERIAL REQUIREMENTS	
QUAN.	SYMBOL	DESCRIPTION	
	⊙	HIGH VOLTAGE SERVICE CONDUIT.	
20'	⊙	LOW VOLTAGE CONDUIT TO SWITCHBOARD. <i>2-4"</i>	
	⊖	GROUNDING ROD (FURNISHED BY EDISON □) (FURNISHED BY CUSTOMER □)	
	⊞	PULL BOX _____ DWG. _____ ITEM	
	⊞	PAD-48" X 54" _____ 72" X 66" _____ 94" X 72" US-170. UGS-500	
	⊞	SLAB BOX -6' X 8' _____ 8' X 10' _____ US-180, UGS-530	
	⊞	SUBSURFACE ENCLOSURE _____ UGS-560, 562, 564 or 566	
1	⊞	HANDHOLE, _____ DWG. _____ UGS-200. <i>EX. HH.</i>	
	⊞	BURD SWITCH (PLASTIC-36" DIA. US-165 □) ENCLOSURE (CONCRETE-36" DIA. US-160 □)	
	⊞	BURD TRANSFORMER (PLASTIC-42" DIA. US-150 □) ENCLOSURE (CONCRETE-36" DIA. US-140 □, 42" DIA. US-145 □)	
1	⊞	<i>120/208V 3P 4W PANEL</i>	

CONSTRUCTION REQUIREMENTS	
CHECK	DESCRIPTION
✓	UPPER END OF RISER TO PROJECT <i>3"</i> INCHES ABOVE FLOOR PER UGS-170.
✓	RISER CONDUIT AT POLE SHALL CONFORM TO UGS-160, 161, 162 OR 163; CR-120 FOR CIC. REFER TO UGS-702 FOR GROUNDING METAL RISERS.
✓	UNDERGROUND SERVICE CONDUCTORS FROM AN OVERHEAD SOURCE SHALL EXTEND A MINIMUM OF _____ FEET FROM EACH CONDUIT ENTERING A VAULT OR ENCLOSURE. EDISON INSTALLS UNDERGROUND SERVICE CONDUCTORS FROM AN UNDERGROUND SOURCE.
✓	STANDARD CONDUIT ENTRANCE PER UGS-130.
	ALL PRECAST PADS AND BOXES TO BE PLACED ON 6" OF COMPACTED CRUSHED ROCK (1/2" MIN. - 1 1/2" MAX.)
	IN ALL CASES THERE SHALL BE A 3 FT. CLEARANCE BETWEEN PADMOUNT TRANSFORMER AND ANY COMBUSTIBLE WALL; 8 FT. CLEARANCE REQUIRED FROM DOOR SIDE OF PADMOUNT TRANSFORMER; 12" MIN. CLEARANCE REQUIRED BETWEEN TRANSFORMER PAD AND ANY UNDERGROUND OBSTRUCTION.
✓	CUSTOMER SHALL PROVIDE ADEQUATE PROTECTION FROM VEHICULAR DAMAGE. DWG. UGS-830.
✓	CUSTOMER SHALL PROVIDE A TRENCH <i>36"</i> DEEP AND <i>18"</i> INCHES WIDE. CUSTOMER SHALL ALSO PROVIDE BACKFILL PER EDISON STANDARDS.
	CUSTOMER SHALL PROVIDE 3" CONCRETE PROTECTION UGS-120.
✓	CONDUIT TO BE INSTALLED PER S.C.E. CO ELECTRICAL SERVICE REQ. PAGES 218, 219, 242, 243 AND UGS-110 & 100 1
	ALL STRUCTURES SHALL MEET REQUIREMENTS OF EDISON ELECT. SERV. REQMENTS. & UND.G. STRUCTURES BOOK (UGS). CONCRETE FLOORED STRUCTURES TO BE WATER TIGHT.

PLAN SHOWING PROPOSED ELECTRIC UNDERGROUND LAYOUT FOR CUSTOMER INSTALLATION

UNDERGROUND SERVICE ALERT
1-800-422-4133
 Call USA/SC
 For Underground Locating
 2 Working Days Before You Dig



THIS PLAN APPROVED AS TO LOCATION AND TYPE OF ELECTRIC SUBSTRUCTURES		
Dwg./Rev	Developer's Signature	Date
Original		
Rev. 1		
Rev. 2		
Rev. 3		

CHANGES IN THESE PLANS WILL REQUIRE AN ADDITIONAL 4 TO 6 WEEKS


SAP TO # *363285* INVENTORY *61-59C*
 DWO *6642-2265* MAP PAGE NO. *671 G-1*
 HIGH VOLTAGE: *16 KV MADISON* LOW VOLTAGE: *120/208V*
 LOCATION: *SANTA MONICA* DISTRICT _____
 FOR: *SANTA MONICA T.V. STUDIO (CITY)*
 ADDRESS: *1654-19th Street*
SANTA MONICA, CA 90404
 DRAWN BY *WINGO* APPROVED BY _____
 DATE *8-7-09* J.I. NO. *9-2058*
 SOUTHERN CALIFORNIA EDISON COMPANY LAST REVISION



Fire Hydrant Flow Test Request Form
 City of Santa Monica
 Civil Engineering & Architecture Division
 1655 Main St. Room 113
 Santa Monica, CA 90401
 Phone: (310) 458-8721 extension 5849
 FAX: (310) 575-3598

Date Requested: 05-24-09 2:08 PM
 EPM Contact: Carlos Rosales

Date of Test: 9-1-09 Test No.: 568
 Test Location: 1654 19th Street
 Witnessed By: Ruben De La Cruz
 Remarks:



Flow Test Request Procedure:
 Please print and mail the fire hydrant you wish to have flow tested. Return the request form by mail or deliver it in person. Return the request form by mail or deliver it in person. Return the request form by mail or deliver it in person. Return the request form by mail or deliver it in person. Return the request form by mail or deliver it in person.

Hydrant No.	Size Class	Flow Class	Flow (gpm)
1	4"	30	2353
2	4"	22	2015

Static Press: 90
 Residual Press: 68
 Total Res Flow: 4368

Attach Business Card or Write Business Address Here:
Karen Dormerchie
City of Santa Monica
Architecture Team
ext. 2619

- Legend**
- ◊ Fire Hydrant
 - Water Valve
 - Water Meter
 - ACP Asbestos Cement Pipe
 - CIP Cast Iron Pipe
 - CIP-CI Cast Iron Pipe-Cement Lined
 - DIP Ductile Iron Pipe
 - SS Stainless Steel

CITY TV TENANT IMPROVEMENTS

EXHIBIT "E"



ENVIRONMENTAL, INC.

Engineering and Environmental Consultants

Revised: August 26, 2010
May 24, 2010

Ms. Karen Domerchie, Civil Engineering Associate
City of Santa Monica, Architecture Services Section
1437 4th Street, Suite 300
Santa Monica, CA 90401

karen.domerchie@smgov.net

RE: Limited Bulk Asbestos and Lead Sampling
Former Auto Body Shop
1654 19th Street, Santa Monica, CA 90404
SCA Project No.: N-9871

Dear Ms. Domerchie:

Per your request, SCA performed a pre-renovation hazardous materials survey of a former Auto Body Shop at the above-referenced address, which is slated for conversion to a television studio. Ms. Lori Kennington, a Cal/OSHA Certified Asbestos Consultant and CDPH Lead Project Monitor, collected the bulk asbestos and lead samples on May 13, 2010.

Asbestos

The bulk asbestos samples were analyzed by EMS Laboratories in Pasadena, CA, an NVLAP-accredited laboratory, by polarized light microscopy (PLM), EPA Method 600/R-93/116.

SCA collected bulk asbestos samples of suspect Asbestos Containing Materials (ACM) that may potentially be impacted by the renovations. SCA's asbestos sampling results are presented in the table below.

**Former Auto Body Shop - 1654 19th Street, Santa Monica
Asbestos Bulk Sample Analytical Results: 5/13/10**

Location	Material Description	SCA Sample ID	Sample Results	Quantity of Material
Roof	Black/gray tar-like roof penetration mastic associated with pipes and vents.	PENMAS-01-01, -02, -03	7% CH	10 SF
	Black/gray built-up rolled roofing with tar/felt layer.	RFROLL-02-01, -02, -03	ND	N/A
Office Areas	Gypsum wall and ceiling board and associated joint compound.	WLSH-03-01, -02, -03, -04, -05	ND	N/A
	Non-suspect yellow carpet mastic.	CARMAS-NNN	---	N/A
Warehouse	White putty-like door caulking associated with west Warehouse door.	CAULK-04-01	1-2% CH	< 1 SF
	Black rubber door caulking at east Warehouse door threshold.	CAULK-NNN	---	N/A
Restrooms	Grout associated with ceramic wall tiles.	GROUT-05-01, -02, -03	ND	325 SF

CH denotes Chrysotile asbestos detected in sample; ND denotes sample is "non-detect" for asbestos; SF denotes "square feet"; and N/A denotes "not applicable".

Prior to any renovations affecting the ACM, the National Emission Standard for Hazardous Air Pollutants (NESHAP) mandated by the Environmental Protection Agency (EPA) and locally enforced by the South Coast Air Quality Management District (SCAQMD) require that all buildings be inspected for asbestos-containing materials, and materials subject to damage or which will be made friable, be removed.

Federal Occupational Safety and Health Administration (OSHA) regulations, locally enforced by Cal/OSHA, define ACM as substances that contain greater than 1% asbestos. Cal/OSHA also mandates special training, medical exams, personal protective equipment and record keeping for employees working with ACM.

Asbestos was identified in both the white door caulking around the west Warehouse door and black roof penetration mastic.

Lead

A total of three (3) bulk lead samples of paints and ceramic tiles were also collected by SCA within the Warehouse. These samples were analyzed for lead content in accordance with NIOSH method 7420, using flame atomic absorption. They were analyzed by EMS Laboratories, in Pasadena, CA. The HUD guideline level for lead in paints is 5,000 parts per million (ppm) of lead, and the current Consumer Products Safety Commission (CPSC) standard for lead in paints is 90 ppm.

Please note that although lead-based paints (LBP) defined against the HUD Standard, Cal/OSHA's Construction Lead Standard, 8 CCR 1532.1, applies to all paints with any measured lead content, requiring dust control measures to reduce airborne and ingestion lead dust hazards. SCA's bulk lead sampling results are presented in the table below.

Former Auto Body Shop - 1654 19th Street, Santa Monica
Lead Bulk Sample Analytical Results: 5/13/10

Location	Material Description	SCA Sample ID	Sample Results (ppm)
Warehouse	Blue interior wall paint on gypsum wallboard – intact.	Pb-BL-1	< 46
	White interior wall paint on gypsum wallboard – intact.	Pb-WH-2	< 46
Restrooms	4" x 4" white, glazed ceramic wall tiles	Pb-GLAZE-3	110

Since elemental lead is a suspect carcinogen and known teratogen and neurotoxic in high doses, lead-containing materials need to be identified prior to the on-set of renovation activities. Using combinations of engineering controls and personal protective equipment, lead-containing materials can be remediated safely. Several sources of applicable standards are listed as follows:

- Lead exposures in the workplace are regulated by Cal/OSHA, which has certain regulatory requirements for identifying and controlling potential lead exposures. Currently applicable regulations for the construction industry have been adopted by Cal/OSHA (8 CCR 1532.1) from the Federal OSHA regulations, with possibly more stringent regulations being drafted by Cal/OSHA. The current OSHA 8-hour Permissible Exposure Level (PEL) for lead is 50 µg/M³.
- Current EPA and Cal/EPA regulations do not require LBP to be removed prior to renovations, unless loose and peeling. Provided that the paints are securely adhered to

the substrates (i.e., non-flaking or non-peeling), disposal of the debris may be handled in California as non-hazardous and non-RCRA waste, pending characterization of the waste.

- In California, loose and peeling LBP or other wastes exceeding the Total Threshold Level Concentration (TTL) of 1,000 ppm ($\mu\text{g/g}$) would be required to be disposed of as non-RCRA hazardous waste. However, if the leachable lead contents of the wastes exceed the Soluble Threshold Level Concentration (STLC) of 5 mg/liter, the wastes have to be disposed of as RCRA waste.
- The major definitions of LBP or lead-coated surfaces are listed as follows:
 - HUD defines LBP as paint that contains either = 0.5% by weight of lead (5,000 parts per million), or = 1 mg/cm².
 - Consumer Product Safety Commission (CPSC) prohibits the manufacturing of paint that contains more than 600 ppm (0.06%) of lead. This was further reduced to 90 ppm in August 2009.
- Please note that compliance to Cal/OSHA's Construction Lead Standard is required for all paints and glazing with any measurable lead content.
- Lead is on the "Proposition 65" list, given its toxic potential in causing reproductive hazards.
- The California Department of Public Health's (CDPH) regulation 17 CCR Sections 35001 through 36100 requires all demolition, stabilization or scraping for repainting of paints or glazing defined under the HUD Guidelines as "lead-based paints" to be completed by Certified Lead Workers and Supervisors. This regulation affects all public, non-industrial buildings, including schools, offices, and housing for permanent renovations, expected to last over 20 years. Furthermore, the CDPH regulations require the use of dust controls, medical surveillance and respiratory protection, oftentimes exceeding the minimum standards outlined under Cal/OSHA's regulation 8 CCR 1532.1.

Manual demolition of lead-glazed ceramic tiles would be considered a "trigger task" under Cal/OSHA's Lead Construction Standard, 8 CCR 1532.1, requiring exposure monitoring, respiratory protection, and dust controls during demolition.

Limited Bulk Asbestos and Lead Sampling for the City of Santa Monica, Architecture Services Section
Former Auto Body Shop
1654 19th Street, Santa Monica, CA 90404
SCA Project No.: N-9871

Attached are SCA's field data sheets, a sample location sketch and laboratory results. Please feel free to contact us at (310) 258-0460 if you have any questions regarding this letter.

Sincerely,
SCA ENVIRONMENTAL, INC.



Lori Kennington, CAC
CDPH Lead Project Monitor
Project Manager

Rev.: MO

Attachments: Material Sampling Data Sheet
 Sample Location Sketch
 Laboratory Results and Chain of Custody
 SCA Staff Certifications
 Photographs

File/Disk:L-9871 Ltr Rpt 082610R/ N-9871 fileserve

CITY OF SANTA MONICA - ARCHITECTURE SERVICES SECTION

BLDG NAME: 1654 19th St, SANTA MONICA - FORMER AUTO BODY SHOP

SCA Environmental, Inc. Asb Material/Sampling Data Sheet

BLDG NO: [] [] [] [] [] [] [] [] [] []

DEPT CODE: [] [] [] [] [] [] [] [] [] []

Date Inspected: 05/13/10


Page 1 of 1

PROJECT NO. N9871 [] [] [] [] [] [] [] [] [] []

Inspected By: L. KENNEDY

Sample ID (include BLDG no.)			Sample Location Data				Material Comments (building wide)	
HOMOGENEOUS MATERIAL ID	Linked Material No.	Sample Type B Sub-D No.	Functional Space		Room or Space Number	DWG ID	Material Comments (building wide)	
			Space/Room Type	Floor Level				
(+) PENMAS	01	01		Roof			BLACK / GRAY TAR-LIKE ROOF PENETRATION MASTIC ASSOCIATED WITH APES AND VENTS	
↓	↓	02		↓			~ 10 SF	
		02						
NFROLL	02	01		Roof			BLACK / GRAY BUILT-UP ROLLED ROOFING AND FELT LAYER	
↓	↓	02		↓			~ 3,720 SF	
		03						
WLSH	03	01		1st Floor			GYPSUM WALL AND CEILING BOARD AND ASSOCIATED JOINT COMPOUND	
↓	↓	02		1st Floor				
		03		Attic				
		04		Attic				
		05		Attic			~ 2,975 SF	
(+) CAULK	04	01		South Door			WHITE PUTTY-LIKE DOOR CAULKING	
							~ 4 LP x 0.5 SF	
GROUT	05	01		Men's Restroom			WALL GROUT ASSOCIATED WITH CERAMIC TILES IN RESTROOMS	
↓	↓	02		↓				
		03					~ 325 SF	
CARMA5	NNN			OFFICES			Non-SUSPECT YELLOW CARPET MASTIC	
CAULK	NNN						BLACK RUBBERIE DOOR CAULKING AT NORTH DOOR THRESHOLD	

Comments: (please number each comment and reference above) WOOD NAILED IN BASEBOARDS, NO VINYL FLOOR TILES OBSERVED, CONCRETE FLOOR THROUGHOUT MAIN SPACE, BRICK PERIMETER WALLS, FLASHINGS NAILED IN - SILICONE CAULKING ON NAILS.



Title: 659 19th Street, Santa Monica
 Project: City of Santa Monica Hazard Survey
 Drawn By: Carl Cunningham
 Checked By: [Signature]
 Date: 5/13/10 Scale: 1 Box = 2' (AS SHOWN)

SCA
 ENVIRONMENTAL, INC.
 5777 W. Century Blvd., Ste 106
 Los Angeles, CA 90045
 Tel: (310) 258-0480
 Fax: (310) 962-0736

KEY:
 ○ = CALKING (ACM)
 ○ = PENETRATION MASTIC (ACM)
 ● = BALLASTS
 ○ = 30 Fluorescent Light Tubes




PLM Report

Report No: 137726 Customer: SCA Environmental
 Date: May 19, 2010 5777 W. Century Blvd., Ste 1055
 Date Received: May 13, 2010 Los Angeles, CA 90045
 Date Analyzed: May 18, 2010 Attention: Mark Osborn
 Date/Time Collected: May 13, 2010 Reference: N9871 CSM
 Subject: Polarized Light Microscopy Analysis for Asbestos 20 Samples
 Methodology: "Method for Determination of Asbestos in Bulk Building Materials." EPA 600/R-93/116
 Accredited: NVLAP Lab Code 101218-0
 Certified: California Department of Health Services Environmental Testing Laboratory ELAP 1119
 County Sanitation Districts of Los Angeles County, Lab ID No. 10120

Quality Control Sample (SRM 1866 Glass Fibers as the blank): None Detected

Sample ID	Location / Description	Visual Description	Asbestiform Minerals	Other Fibrous Materials
PENMAS-01-01	NON-FRIABLE	BLACK/GRAY TAR LIKE	CHRYSTOLE 7%	NONE DETECTED
PENMAS-01-02	NOT ANALYZED - STOP AT FIRST POSITIVE			
PENMAS-01-03	NOT ANALYZED - STOP AT FIRST POSITIVE			
RFROLL-02-01	NON-FRIABLE	BLACK TAR LIKE	NONE DETECTED	CELLULOSE <1%; FIBERGLASS 15%
RFROLL-02-02	NON-FRIABLE	WHITE/BLACK TAR LIKE	NONE DETECTED	FIBERGLASS 15%
RFROLL-02-03	NON-FRIABLE	WHITE/BLACK TAR LIKE	NONE DETECTED	NONE DETECTED
WLSH-03-01 DW	NON-FRIABLE	WHITE/BROWN FIBROUS	NONE DETECTED	CELLULOSE 15%
WLSH-03-01 JC	NON-FRIABLE	WHITE SOLID	NONE DETECTED	CELLULOSE - LESS THAN 1%
WLSH-03-02 DW	NON-FRIABLE	WHITE/BROWN FIBROUS	NONE DETECTED	CELLULOSE 20%
WLSH-03-02 JC	NON-FRIABLE	WHITE SOLID	NONE DETECTED	NONE DETECTED
WLSH-03-03 DW	NON-FRIABLE	WHITE/BROWN FIBROUS	NONE DETECTED	CELLULOSE 15%
WLSH-03-03 JC	NON-FRIABLE	WHITE SOLID	NONE DETECTED	NONE DETECTED
WLSH-03-04 DW	NON-FRIABLE	WHITE/BROWN FIBROUS	NONE DETECTED	CELLULOSE 15%; FIBERGLASS <1%
WLSH-03-04 JC	NON-FRIABLE	BLACK SOLID	NONE DETECTED	NONE DETECTED
WLSH-03-05 DW	NON-FRIABLE	WHITE/BROWN FIBROUS	NONE DETECTED	CELLULOSE 15%
WLSH-03-05 JC	NON-FRIABLE	WHITE SOLID	NONE DETECTED	NONE DETECTED


 Wesene Sebat, Optical Microscopist
 BMK/ml


 B.M. Kolk, Laboratory Director

The EPA method is a semi-quantitative procedure. The detection limit is between 0.1 - 1% by area and is dependent upon the size of the asbestos fibers, the means of sampling and the matrix of the sampled material.

The test results reported are for the sample(s) delivered to us and may not represent the entire material from which the samples was taken. The EPA recommends three samples or more be taken from a "homogenous sampling area" before friable material is considered non-asbestos-containing.

** Negative floor tile samples may contain significant amounts (>1%) of very thin asbestos fibers which cannot be detected by PLM. Confirmation by XRD or TEM is recommended by the EPA (Federal Register Vol. 59, No. 146).


This report, from a NIST-accredited laboratory through NVLAP, must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. government. This report shall not be reproduced, except in full, without the written approval of EMS Laboratories.

Samples were received in good condition unless otherwise noted.

PLM Report

Report No: 137726 Client: SCA Environmental

Sample ID	Location / Description	Visual Description	Asbestiform Minerals	Other Fibrous Materials
CAULK-04-01	NON-FRIABLE	WHITE/BLACK RUBBERY	CHRYSTILE 1-2%	NONE DETECTED
GROUT-05-01	NON-FRIABLE	WHITE SOLID	NONE DETECTED	NONE DETECTED
GROUT-05-02	NON-FRIABLE	WHITE SOLID	NONE DETECTED	NONE DETECTED
GROUT-05-03	NON-FRIABLE	WHITE SOLID	NONE DETECTED	NONE DETECTED



Wesene Sebhat, Optical Microscopist
 BMK/mt



B.M. Kolk, Laboratory Director

The EPA method is a semi-quantitative procedure. The detection limit is between 0.1 - 1% by area and is dependent upon the size of the asbestos fibers, the means of sampling and the matrix of the sampled material.

The test results reported are for the sample(s) delivered to us and may not represent the entire material from which the samples was taken. The EPA recommends three samples or more be taken from a "homogenous sampling area" before friable material is considered non-asbestos-containing.

** Negative floor (ie samples may contain significant amounts (>1%) of very thin asbestos fibers which cannot be detected by PLM. Confirmation by XRD or TEM is recommended by the EPA (Federal Register Vol. 59, No. 146).

This report, from a NIST-accredited laboratory through NVLAP, must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. government. This report shall not be reproduced, except in full, without the written approval of EMS Laboratories.

Samples were received in good condition unless otherwise noted.

DATE: May 19, 2010

Page 1 of 2

CLIENT: SCA Environmental
5777 W. Century Blvd. #1055
Los Angeles, CA 90045

ATTENTION: Mark Osborn

REFERENCE: N9871
CSM

REPORT NO: 137721

DATE OF SAMPLE COLLECTION: May 13, 2010

DATE RECEIVED: May 13, 2010

DATE ANALYZED: May 17, 2010

ACCREDITATION: American Industrial Hygiene Association (101634),
Environmental Lead NLLAP
California Dept. of Health Services ELAP 1119

SUBJECT: ANALYSIS OF THREE BULK SAMPLE(S) FOR LEAD

The sample(s) was/ were identified as: Pb-BL-1
Pb-WH-2
Pb-GLAZE-3

The bulk sample(s) was/ were analyzed for lead by digestion according to EPA method 3050M and analysis by EPA method 7420.

The results of the analyses and the detection limit(s) are summarized on the following page(s), accompanied by the chain of custody.

Respectfully submitted,
EMS Laboratories, Inc.



A. J. Kolk Jr.
Technical Director
AJK/mt

Method 3050 requires 1 to 2 grams of sample. The method is being used with paint chips with less than 1 gram sample and is designated 3050M.

Note: The report shall not be reproduced, except in full, without the written approval of EMS Laboratories, Inc.

Note: The results of the analysis are based upon the sample submitted to the laboratory. No representation is made regarding the sampling area other than that implied by the analytical results for the immediate vicinity of the samples analyzed as calculated from the data presented with those samples. All the analytical quality control data meet the requirement of the procedure unless otherwise indicated. Any deviation or exclusion from the test method is noted in this cover letter. Unless otherwise noted in this cover letter the samples were received properly packaged, clearly identified and intact.

Results have not been corrected for field blank or EMS Blank for lead samples that fall under the AIHA ELPAT program.

Laboratory Report**Sample Info**

Date of Analysis: 5/17/2010
Lab ID: 137721
Client: SCA Environmental, Inc.
Date Received: 5/13/2010
Project Number: N-9871
Analyte: Pb
Matrix: PAINT CHIP
Method: EPA 3050M/7420
Comments:

Reporting Limit (mg): 0.007
Method blank (mg): <0.007

Sample Results

Sample Name	Bulk Weight (g)	Pb Weight (mg)	Pb Concentration (ppm)
PB-BL-1	0.1516	< 0.007	< 46
PB-WH-2	0.1508	< 0.007	< 46
PB-GLAZE-3	0.5241	0.059	110

Chemist: *JK*

DEPARTMENT OF INDUSTRIAL RELATIONS

**DIVISION OF OCCUPATIONAL SAFETY AND HEALTH
ASBESTOS CONSULTANT and TRAINER APPROVAL UNIT**2211 Park Towne Circle, Suite 1
Sacramento, CA 95825
Tel: (916) 574-2993 Fax: (916) 483-0572

605101959C

124

SCA Environmental, Inc.

Mark H Osborn

5777 W Century Blvd, 1055

Los Angeles

CA 90045

May 05, 2009

Dear Certified Asbestos Consultant or Technician:

Enclosed is your certification card. **To maintain your certification, please abide by the rules printed on the back of the certification card.**

Your certification is valid for a period of one year. If you wish to renew your certification, you must apply for renewal at least 60 days before the expiration date shown on your card. [8 CCR 341.15(h)(1)].

Please hold and do not send copies of your required AHERA refresher renewal certificates to our office until you apply for renewal of your certification. Certificates must be kept current if you are actively working as a CAC or CSST. The grace period is only for those who are not actively working as a CAC or CSST.

Please inform our office at the above address, fax number or actu@dir.ca.gov of any changes in your contact/mailling information within 15 days of the change.

Sincerely,

Jeff Ferrell
Senior Industrial Hygienist

JF/ms

Attachment: Certification Card
cc: File

State of California
Division of Occupational Safety and Health
Certified Asbestos Consultant

Mark H Osborn

Name

Certification No. 96-1959Expires on 05/24/10


This certification was issued by the Division of Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.



Mr. Mark H. Osborn
SCA Environmental, Inc.
5777 West Century Boulevard, Suite 1055
Los Angeles, California 90045



State of California Department of Public Health

Lead-Related Construction Certificate	Certificate Type	Expiration Date
	Project Monitor	08/22/2010



Mark H. Osborn ID #: 6167

Institute of Hazardous Materials Management



Certifies that

Mark H. Osborn

has successfully met all requirements of education, experience and examination, and is hereby designated a

**Certified Hazardous Materials Manager
Master Level**

October 1998

9353

December 31, 2011

Certified

Number

Expiration Date

John H. Frick
Executive Director

So long as this credential is renewed according to schedule and is not otherwise revoked.

DEPARTMENT OF INDUSTRIAL RELATIONS
DIVISION OF OCCUPATIONAL SAFETY AND HEALTH
ASBESTOS CONSULTANT and TRAINER APPROVAL UNIT

2211 Park Towne Circle, Suite 1
Sacramento, CA 95825
Tel: (916) 574-2993 Fax: (916) 483-0572



812264472C

322

December 16, 2009

SCA Environmental, Inc.
Lori E Kennington
5777 W. Century Blvd., #1055
Los Angeles CA 90045

Dear Certified Asbestos Consultant or Technician:

Enclosed is your certification card. To maintain your certification, please abide by the rules printed on the back of the certification card.

Your certification is valid for a period of one year. If you wish to renew your certification, you must apply for renewal at least 60 days before the expiration date shown on your card. [8 CCR 341.15(h)(1)].

Please hold and do not send copies of your required AHERA refresher renewal certificates to our office until you apply for renewal of your certification. Certificates must be kept current if you are actively working as a CAC or CSST. The grace period is only for those who are not actively working as a CAC or CSST.

Please inform our office at the above address, fax number or actu@dir.ca.gov of any changes in your contact/mailling information within 15 days of the change.

Sincerely,

Jeff Ferrell
Senior Industrial Hygienist

State of California
Division of Occupational Safety and Health
Certified Asbestos Consultant

JF/ms

Attachment: Certification Card
cc: File

Lori E Kennington

Name

Certification No. 08-4472

Expires on 01/15/11





This certification was issued by the Division of Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.

Ms. Lori E. Kennington
SCA Environmental, Inc.
5777 West Century Boulevard, Suite 1055
Los Angeles, California 90045

State of California Department of Public Health
Lead-Related Construction Certificate

Certificate Type	Expiration Date
Project Monitor	08/06/2010
Sampling Technician	08/06/2009



Lori E. Kennington ID #: **19525**

CERTIFICATE OF TRAINING

8-HOUR ANNUAL REFRESHER HAZARDOUS WASTE OPERATIONS

This certificate certifies that

LORI KENNINGTON – SCA ENVIRONMENTAL

Has satisfactorily completed, and shown an understanding of, 8 hours annual refresher of Hazardous Waste Operations Training, as required by Federal Occupational Safety and Health Administration Regulation 29 CFR 1910.120

SCA

ENVIRONMENTAL, INC.

334 19th Street
Oakland, CA 94612
TEL: (510) 645-6200
eFAX: (415) 962-0736


Date: 9/17/09

Expiration Date: 9/17/10

Approved by: Glenn R. Cass, PE,


CIH

SCA Project No.: SOK-09




Topic	Hours	Date	Instructor(s)/ Training Program
AIHA Course 2371 "Indoor Air Quality Solutions" and misc. refresher items	8	9/17/09	AIHA Course 2371

Photographs



Black/gray tar-like penetration mastic associated with pipes and vents located on the roof, totaling approximately 10 square feet [Sample I.D. PENMAS-01-01, -02, -03 containing 7% Chrysotile].



White putty-like door caulking associated with west warehouse door, totaling approximately less than 3 square feet [Sample I.D. CAULK-04-01 containing 1-2% Chrysotile].

**NOTICE:
CITY POLICY ON DOING BUSINESS WITH ARIZONA FIRMS**

CITY OF SANTA MONICA

NOTICE TO APPLICANTS, BIDDERS, PROPOSERS AND OTHERS SEEKING TO DO
BUSINESS WITH THE CITY OF SANTA MONICA

The City Council of the City of Santa Monica adopted Resolution No. 10479 (CCS) on May 25, 2010, which requires a review of all current and likely future agreements and contracts with Arizona-based businesses to examine the feasibility of acquiring such products and services elsewhere while the Arizona law remains in effect.

Additionally, Council directed staff to require vendors offering goods or services to the City of Santa Monica to complete and sign the attached disclosure form; this applies to all solicitations, including but not limited to, bids and proposals. Please review, sign and submit the form with your bid packet prior to the closing date of bid.

Failure to return this form or inability to certify as to its provisions will render your bid or proposal non-responsive.

State of Arizona Disclosure Form - see next page.

**CITY OF SANTA MONICA
STATE OF ARIZONA DISCLOSURE FORM**

**TO BE COMPLETED BY ALL VENDORS PROVIDING GOODS AND
SERVICES TO THE CITY OF SANTA MONICA**

I certify that (check all that apply):

Our company has no presence, interest or professional business relationships with or in the State of Arizona nor conducts business with individual subcontractors located within the State of Arizona.

Our company's headquarters are located in the State of Arizona.

Our company's branch offices, warehouses or manufacturing facilities are located in the State of Arizona.
Number of branch offices, warehouses or manufacturing facilities: _____
If more than one, attach a list of additional locations, including the physical address of each location.

Name of Location: _____
 Branch Office Warehouse Manufacturing Facility Other _____

Street Address: _____

City: _____ State: _____ Zip Code: _____

Products or services will be manufactured or performed by a subcontractor whose business is located within the State of Arizona.

***** PORTION BELOW TO BE COMPLETED BY ALL VENDORS *****

Please list any and all subcontractors that your company conducts business with.
If more than one, attach a list of additional subcontractors, including the physical address of each location.

Our company does not work with ANY subcontractors.

Name of Subcontractor: _____

Street Address: _____

City: _____ State: _____ Zip Code: _____

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct.

Signed: _____ Date: _____

Printed name: _____ Title: _____

Name of Company: _____

Street Address of Headquarters: _____

City: _____ State: _____ Zip Code: _____

Telephone # (including area code): _____ Email: _____